DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	TUBULAR STEEL Ø (IN) (LB / FT) FOUNDATION	3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
WASHINGTON VT 110							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.360	A	W11-6H	30	30		SNOWMOBILE HINGED			1				X															
NB	5.370	B	W1-6	48	24		LARGE ARROW RIGHT			1				X															
NB	5.379	C	VR-017	24	30								1		X											TURNPIKE RD TH-29			
		C	VR-017	24	30			5.00								1		X											E-141
NB	5.387	D	R1-1	30	30								0 ~~1~~		X											TURNPIKE RD TH-29			
		D	R1-1	30	30			0 ~~6.25~~								0 ~~1~~		X								X			
NB	5.530	A	VD-018	30	18		WASHINGTON EAST BARRE 4			1				X															
NB	5.610	A	S3-1	30	30		SCHOOL BUS STOP AHEAD			1				X															
NB	5.650	A	R2-1	24	30								1		X															
		A	R2-1	30	36			7.50								1		X									6		
NB	5.690	A	D1-1A	72	12		WEST CORINTH 7 --->			1				X															
NB	5.720	C	VR-017	24	30								1		X											WEST CORINTH RD TH-1			
		C	VR-017	24	30			5.00								1		X											E-141
NB	5.728	D	R1-1	30	30								1		X											WEST CORINTH RD TH-1			
		D	R1-1	30	30			6.25								1		X								X			
							SHEET TOTALS	~~30.00~~	0.00	5	0	0	~~5~~	0	0	5		75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
								23.75					4																
							TOWN TOTALS	320.1	0.0	42.0	3.0	3.0	66	2.0	0.0	73		1095.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Royalton-Barre Town VT110
PROJECT NUMBER: STPG SIGN(23)

FILE NAME: Washington.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: D. Crossley
WASHINGTON SHEET 4

PLOT DATE: 6/15/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard