DIR	MILE-POINT	LOC CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW "A"	NEW "B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	POST RETAIN	POST REMOVE	# NEW POSTS	SQ 1.88	SQ 2.42	SQ 3.35	FOUNDATION	TUB 7.60	TUB 9.00	TUB 10.80	TUB 14.60	SIGN FRAME REQ	REMARKS	DETAIL IN SHS	DETAIL ON SHEET #	DETAIL ON STD SHEET #
WASHINGTON VT 110							FY-FLUORESCENT YELLOW / FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.512	D	R1-1	30	30		STOP						1		X											CREAMERY RD TH-7			
		D	R1-1	30	30			6.25								1		X									X		
NB	6.530	A	R2-1	24	30		SPEED LIMIT 40			1				X															
NB	6.610	A	R2-1	24	30		SPEED LIMIT 50			1				X															
NB	6.790	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		A	S3-1	30	30			6.25								1		X									X		
SB	6.700	F	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 40			1				X															
SB	6.610	F	R2-1	24	30		SPEED LIMIT 40						1		X														
		F	R2-1	30	36			7.50								1		X										6	
SB	6.475	G	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											LOWERY RD TH-4			
		G	VR-017	24	30			5.00								1		X											E-141
SB	6.467	H	R1-1	24	24		STOP						1		X											LOWERY RD TH-4			
		H	R1-1	30	30			6.25								1		X									X		
SB	6.450	F	R2-1	24	30		SPEED LIMIT 40			1				X															
SB	6.310	F	VD-018	30	18		WASHINGTON CHELSEA 9			1				X															
SHEET TOTALS								31.25 SF	0.00 SF	5 EA	0 EA	0 EA	5 EA	0 EA	0 EA	5 EA				75 FT									
TOWN TOTALS								320.1	0.0	42.0	3.0	3.0	66	2.0	0.0	73				1095.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Royalton-Barre Town VT110**
PROJECT NUMBER: **STPG SIGN(23)**

FILE NAME: **Washington.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **D. Crossley**
WASHINGTON SHEET 6

PLOT DATE: **6/15/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **59** OF **80**