DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ORANGE VT110							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.510	A	VW-054L	30	30		HIDDEN DRIVE LEFT			1				X														
SB	1.750	F	VW-054R	30	30		HIDDEN DRIVE RIGHT			1				X														
SB	1.670	F	W1-2R	30	30		RIGHT CURVE				1	1			X	1		X								INSTALL EXISTING SIGN ON NEW POST		
SB	1.640	F	VW-054R	30	30		HIDDEN DRIVE RIGHT			1				X														
SB	0.410	F	M1-5A	24	24								2 ~~1~~		X													
		F	M3-3	12	24			2.00								1		X							GREEN ON WHITE SHEETING	X		
		F	M1-5	30	24			5.00																				E-136B
SB	0.320	F	W11-6H	30	30								2 ~~1~~		X													
		F	W11-6H	30	30		REMOVE PER TRAFFIC OPPS.	6.25								1		X							INSTALL IN CLOSED POSITION			E-153
SB	0.001	F	S1-S	30	30								1		X													
		F	S1-S	30	30			6.25								1		X								X		
							SHEET TOTALS	19.50	0.00	3	1	1	~~3~~	0	0	4		60										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	56.7	0.0	3.0	1.0	1.0	5 9	0.0	0.0	11		165.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Royalton-Barre Town VT110
PROJECT NUMBER: STPG SIGN(23)

FILE NAME: Orange.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: A. Gamble
ORANGE SHEET 2

PLOT DATE: 6/15/2009
DRAWN BY: T. Guazzoni
CHECKED BY: S. Menard