QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

MAINLINE US 4	RAMPS US 4	MAINLINE US 7	RAMPS US 7	MAINLINE VT 279	RAMPS VT 279	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
0	20	0	20	0	10	50	HR	UNIFORMED TRAFFIC OFFICERS	630.10	0
0	20	0	20	0	10	50	HR	FLAGGERS	630.15	0
						1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
						1	LS	TRAFFIC CONTROL	641.10	EST
						1	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST
						1	EA	PORTABLE ARROW BOARD	641.16	EST
0	250	0	0	0	0	250	LF	4 INCH WHITE LINE	646.20	0
0	17,985	0	23,260	0	5,540	46,785	LF	6 INCH WHITE LINE	646.214	0
0	16,920	0	22,885	0	5,140	44,945	LF	6 INCH YELLOW LINE	646.215	0
0	12,305	0	9,690	0	3,375	25,370	LF	12 INCH WHITE LINE	646.24	0
0	0	0	0	0	150	150	LF	12 INCH YELLOW LINE	646.25	0
0	421	0	112	0	100	633	LF	24 INCH STOP BAR	646.26	0
0	230	0	81	0	54	365	EA	LETTER OR SYMBOL	646.30	0
4	0	0	0	0	0	4	EA	RAILROAD CROSSING SYMBOL	646.32	0
250,607	0	257,675	0	0	0	508,282	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	0
0	0	0	0	44,469	0	44,469	LF	DURABLE 6 INCH WHITE LINE, RECESSED THERMOPLASTIC	646.428	0
215,660	0	190,760	0	0	0	406,420	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	0
0	0	0	0	32,269	0	32,269	LF	DURABLE 6 INCH YELLOW LINE, RECESSED THERMOPLASTIC	646.438	0
0	9,775	0	600	0	1,000	11,375	EA	LINE STRIPPING TARGETS	646.76	0
0	0	1,900	0	0	0	1,900	LF	PAINTED CURB	646.81	0
0	0	0	0	0	80	80	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	0
200	0	200	0	100	0	500	HR	SPECIAL PROVISION (TRUCK-MOUNTED ATTENUATOR, AWV/PV)	900.630	0

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: **STATEWIDE**

PROJECT NO.: **NHG MARK (202)**

DESIGN FILE NAME: 09b002.dgn
IPARM FILE NAME: 09b002qs.i
SURVEYED BY:
SQUAD LEADER: A GAMBLE

PLOT DATE: 03-APR-2009
SURVEY DATE:
DRAWN BY: KAS
SHEET: 2 OF 10