

SUMMARY OF QUANTITIES BY ROUTE

ROUTE	TOWN	MM	TO	MM	4" WHITE LINE	4" YELLOW LINE	8" WHITE LINE	8" YELLOW LINE	STOP BAR	LETTER OR SYM.	CROSS WALK	REMOVAL	REMARKS
VT 103	ROCKINGHAM	0.00	-	6.75									MM 0.00 ROCKINGHAM-MM 6.75 ROCKINGHAM 2009 PROJECT (NO WORK)
VT 103	CHESTER	0.00	-	2.00									MM 0.00 CHESTER-MM 2.00 CHESTER 2009 PROJECT (NO WORK)
VT 103	CHESTER	2.00	-	2.60	6,350	6,350	-	-	-	-	-	-	
VT 103	CHESTER	4.27	-	9.88	56,180	47,690	-	-	-	-	-	-	MM 4.27 CHESTER-MM 9.88 CHESTER 2007 PROJECT 50% NEEDS REPAIR
VT 103	CAVENDISH	0.00	-	3.74									MM 0.00 CAVENDISH-MM 3.74 CAVENDISH 2007 PROJECT 50% NEEDS REPAIR
VT 103	LUDLOW	0.00	-	1.29									MM 0.00 LUDLOW-MM 1.29 LUDLOW 2007 PROJECT 50% NEEDS REPAIR
VT 103	LUDLOW	2.86	-	5.78	38,026	32,090	-	-	-	30	-	-	ARROW(6) ONLY(6)
VT 103	MT HOLLY	0.00	-	7.86	83,820	67,775	-	-	-	-	-	-	
VT 103	SHREWSBURY	0.00	-	4.24	45,304	36,520	-	-	60	4	-	-	RR XING (2) PAY ITEM 646.32
VT 103	CLARENDON	0.00	-	1.97	20,804	14,850	250	100	15	-	-	-	
	VT 103 TOTAL				250,484	205,275	250	100	75	34	-	-	
US 4	RUTLAND TOWN	0.00	-	1.23	14,375	13,628	-	375	65	44	-	143	SIGNAL(1) AHEAD(1) ARROW(9) ONLY(5) REMOVAL=ALIGNING ARROW'S AND ONLY'S TO 2003 MUTCD
US 4	MENDON	0.00	-	5.93	69,390	63,235	-	350	-	20		40	ARROW(4) ONLY(4) REMOVAL=ALIGNING ARROW'S AND ONLY'S TO 2003 MUTCD
US 4	KILLINGTON	0.00	-	7.60	93,534	59,814	940	1,100	15	68	-	360	STOP(2) AHEAD(1) ARROW(11) ONLY(11) REMOVAL=ALIGNING ARROW'S AND ONLY'S TO 2003 MUTCD
US 4	BRIDGEWATER	0.00	-	6.00	36,430	-	-	-	-	-	-	-	MM 7.60 KILLINGTON-MM 6.00 BRIDGEWATER 2007 PROJECT 50% OF WHITE NEEDS REPAIR MM 6.00 BRIDGEWATER-MM 5.65 WOODSTOCK 2008 PROJECT
US 4	WOODSTOCK	7.22	-	9.65	25,300	25,300	-	-	-	-	28	-	
US 4	HARTLAND	0.00	-	0.77	8,130	8,130	-	-	-	-	-	-	
US 4	HARTFORD	0.00	-	9.35	99,792	93,544	245	600	12	67	100	348	STOP(2) AHEAD(1) ARROW(10) DBL ARROW(3) ONLY(5) YIELD(2) REMOVAL=ALIGNING ARROW'S AND ONLY'S AND REPLACING YIELD WORDS WITH YIELD MARKINGS PER 2003 MUTCD
	US 4 TOTALS				346,951	263,651	1,185	2,425	92	199	128	47,251	
	SHEET TOTALS				597,435	468,926	1,435	2,525	167	233	128	47,251	

ROUTE QUANTITIES
SHEET 2

PROJECT: STATEWIDE	PROJECT NO.: NHG MARK (203)
DESIGN FILE NAME: 09b004.dgn	PLOT DATE: 17-JUL-2009
IPARM FILE NAME: 09b004r-q2.1	SURVEY DATE:
SURVEYED BY:	DRAWN BY: KAS
SQUAD LEADER: A GAMBLE	SHEET: 4 OF 13