

PAVEMENT MARKINGS TO BE PERFORMED AT THE FOLLOWING LOCATIONS.
 LOCATION MAY BE ADJUSTED BY THE RESIDENT ENGINEER TO ACCOUNT
 FOR FIELD CONDITIONS.

ROAD	TOWN BEGIN	MM BEGIN	TOWN END	MM END	LENGTH	ROAD	TOWN BEGIN	MM BEGIN	TOWN END	MM END	LENGTH	ROAD	TOWN BEGIN	MM BEGIN	TOWN END	MM END	LENGTH		
VT 9	BENNINGTON	0.00	BENNINGTON	3.12	3.12	US 2	BERLIN	0.00	BERLIN	1.39	1.39	US 7	POWNA	0.00	POWNA	7.99	7.99		
VT 9	BENNINGTON	5.90	BENNINGTON	6.87	0.97	US 2	BARRE TOWN	0.00	BARRE TOWN	0.09	0.09	US 7	BENNINGTON	0.00	BENNINGTON	2.16	2.16		
VT 9	WOODFORD	0.00	WOODFORD	8.67	8.67	US 2	E. MONTPELIER	0.00	E. MONTPELIER	4.82	4.82	US 7	DORSET	1.75	DORSET	6.72	4.97		
VT 9	SEARSBURG	3.54	SEARSBURG	5.68	2.14	US 2	PLAINFIELD	0.00	PLAINFIELD	1.49	1.49	US 7	MT TABOR	0.00	MT TABOR	4.18	4.18		
VT 9	WILMINGTON	0.00	WILMINGTON	1.67	1.67	US 2	MARSHFIELD	0.00	MARSHFIELD	8.21	8.21	US 7	DANBY	0.00	DANBY	2.47	2.47		
VT 9	MARLBORO	0.00	MARLBORO	8.30	8.30	US 2	CABOT	0.00	CABOT	6.23	6.23	US 7	WALLINGFORD	0.00	WALLINGFORD	6.48	6.48		
VT 9	BRATTLEBORO	0.00	BRATTLEBORO	4.26	4.26	US 2	DANVILLE	0.00	DANVILLE	1.78	1.78	US 7	RUTLAND TOWN	1.18	RUTLAND TOWN	3.97	2.79		
VT 9	BRATTLEBORO	7.10	BRATTLEBORO	7.25	0.15	US 2	DANVILLE	4.05	DANVILLE	4.76	0.71	US 7	PITTSFORD	0.00	PITTSFORD	7.59	7.59		
			VT 9 TOTAL (MILES)		29.28	US 2	DANVILLE	4.76	DANVILLE	6.50	1.74	US 7	BRANDON	0.00	BRANDON	3.36	3.36		
						US 2	ST JOHNSBURY	4.70	ST JOHNSBURY	8.64	3.94	US 7	BRANDON	4.35	BRANDON	7.45	3.10		
ROAD	TOWN BEGIN	MM BEGIN	TOWN END	MM END	LENGTH	US 2	KIRBY	0.00	KIRBY	0.97	0.97	US 7	LEICESTER	0.00	LIECESTER	3.43	3.43		
VT 78	ALBURGH	0.00	ALBURGH	3.33	3.33	US 2	CONCORD	0.00	CONCORD	10.78	10.78	US 7	SALISBURY	0.00	SALISBURY	4.50	4.50		
VT 78	SWANTON	0.00	SWANTON	6.34	6.34	US 2	LUNENBURG	0.00	LUNENBURG	9.03	9.03	US 7	MIDDLEBURY	0.00	MIDDLEBURY	4.28	4.28		
VT 78	SWANTON	7.38	SWANTON	8.13	0.75	US 2	GUILDHALL	0.00	GUILDHALL	1.16	1.16	US 7	MIDDLEBURY	5.71	MIDDLEBURY	7.48	1.77		
VT 78	HIGHGATE	0.00	HIGHGATE	7.73	7.73							US 7	NEW HAVEN	0.00	NEW HAVEN	6.10	6.10		
VT 78	SHELDON	0.00	SHELDON	1.84	1.84				US 2 TOTAL (MILES)		52.34	US 7	CHARLOTTE	0.00	CHARLOTTE	6.55	6.55		
			VT 78 TOTAL (MILES)		19.99							US 7	SHELBURNE	0.00	SHELBURNE	2.60	2.60		
																	US 7 TOTAL (MILES)	74.32	
ROAD	TOWN BEGIN	MM BEGIN	TOWN END	MM END	LENGTH														
VT 103	CHESTER	2.00	CHESTER	2.60	0.60														
VT 103	CHESTER	4.27	CHESTER	9.88	5.61														
VT 103	CAVENDISH	0.00	CAVENDISH	3.74	3.74														
VT 103	LUDLOW	0.00	LUDLOW	1.29	1.29														
VT 103	LUDLOW	2.86	LUDLOW	5.78	2.92														
VT 103	MT HOLLY	0.00	MT HOLLY	7.86	7.86														
VT 103	SHREWSBURY	0.00	SHREWSBURY	4.24	4.24														
VT 103	CLARENDON	0.00	CLARENDON	1.97	1.97														
			VT 103 TOTAL (MILES)		28.23														
																		MARK 203 TOTAL (MILES)	237.47

NOTES:

1. ALL MARKINGS SHALL BE WATERBORNE TRAFFIC PAINT
2. ALL MARKINGS SHALL BE PLACED WHERE EXISTING MARKINGS ARE LOCATED EXCEPT WHERE EXISTING STENCILS OR MARKINGS DO NOT CONFORM WITH DETAIL DRAWINGS, EXISTING MARKINGS SHALL BE REMOVED PRIOR TO PLACING NEW MARKINGS
3. HAND WORK MUST BE DONE WITH A SPOTTER AT ALL TIMES
4. CONE TAPERS SHALL BE USED TO DIRECT TRAFFIC AROUND WORKERS AND WET PAINT IN TURN LANES
5. EXISTING CENTERLINE MARKINGS WILL BE REMOVED FROM APPROX. MM 1.65 MENDON TO APPROX. MM 2.05 KILLINGTON. CENTERLINE RUMBLE STRIPS WILL BE INSTALLED AT APPROX. ONE FOOT OFF EXISTING LOCATION OF CENTERLINE (SEE DETAIL ON SHEET 8). NEW CENTERLINE SHALL BE PAINTED OVER THE RUMBLE STRIPS.

INCLUDES TURN LANES AND CLIMBING LANES
 INCLUDES 8 INCH WHITE GORE MARKINGS
 INCLUDES 8 INCH YELLOW PAINTED ISLANDS

PAVEMENT MARKING LOCATION DETAIL	PROJECT: STATEWIDE	PROJECT NO.: NHG MARK (203)
	DESIGN FILE NAME: 09b004.dgn IPARM FILE NAME: 09b004det.t SURVEYED BY: SQUAD LEADER: A GAMBLE	PLOT DATE: 17-JUL-2009 SURVEY DATE: DRAWN BY: KAS SHEET: 7 OF 13