DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
STAMFORD VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN													ALL MILE MARKERS SHOWN WERE SALVAGED ONTO THE NEW POSTS.						"SHS"-STANDARD HIGHWAY SIGNS			
																				ALL STREET SIGNS SHOWN WERE SALVAGED ONTO THE NEW POSTS								
NB	0.016	A	VD-421A	60	48								1		X														
		A	VD-421A	30	24			5.00								1		X									5		
NB	0.043	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X								X		
NB	0.043	A	M3-1S	24	12		NORTH						1		X														
		A	M1-5	30	24		VERMONT 100						1																
		A	M1-5A	24	24		VERMONT 8						1																
NB	0.081	A	M3-1	24	12			2.00								2		X							#1A	INSTALL ASSEMBLY 200 FEET NORTH OF EXISTING ASSEMBLY. GREEN ON WHITE SHEETING	X	7	
		A	M1-5	30	24			5.00																				E-136B
		A	M3-1	24	12			2.00																		GREEN ON WHITE SHEETING	X		
		A	M1-5	24	24			4.00																				E-136B
NB	0.125	A	VR-128	36	36								1		X														
		A	VR-601	30	36			7.50 ~~7.00~~								1		X									6	
NB	0.150	A	VR-654	24	24								1		X														
							SHEET TOTALS	30.50 ~~30.00~~	0.00	0	0	0	7	0	0	5		75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	455.0	0.0	16.0	5.0	5.0	75	0.0	0.0	83		1245.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Stamford-Andover VT100
PROJECT NUMBER: STPG SIGN(20)

FILE NAME: Stamford.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: J. Kelly
STAMFORD SHEET 1

PLOT DATE: 8/5/2009
DRAWN BY: T. Guazzoni
CHECKED BY: T. Guazzoni
SHEET 9 OF 198