DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STAMFORD VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	1.007	F	S1-1YG	30	30		SCHOOL PENTAGON			1				X															
SB	1.007	F	W16-7YG	24	12		DOWN LH ARROW			1																			
SB	0.965	F	S1-1YG	30	30		SCHOOL PENTAGON			1				X															
SB	0.965	F	W16-7YG	24	12		DOWN LH ARROW			1																			
SB	0.880	F	S5-2	24	30		END SCHOOL ZONE	5.00								1		X								INSTALL ACROSS ROAD FROM SCHOOL SPEED LIMIT 30 WHEN FLASHING	X		
SB	0.819	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											TH-2, JEPSON RD			
		G	VR-017	24	30			5.00								1		X											E-141
SB	0.811	H	R1-1	30	30		STOP						1		X											TH-2, JEPSON RD			
		H	R1-1	30	30			6.25								1		X								INSTALL SIGN CLOSER TO VT-100	X		
SB	0.795	F	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
SB	0.780	F	W1-4L R	30	30			6.25								1		X								INSTALL 80 FEET SOUTH OF EXISTING LOCATION	X		
SB	0.560	F	R2-1	24	30		SPEED LIMIT 35						1		X														
		F	R2-1	24	30			5.00								1		X									X		
SB	0.465	F	W1-6	48	24			8.00								2		X								INSTALL BETWEEN DRIVEWAY AND EXISTING LARGE ARROW	X		
SB	0.460	E	W1-6	48	24								1		X														
							SHEET TOTALS	35.50 SF	0.00 SF	4 EA	0 EA	0 EA	5 EA	0 EA	0 EA	7 EA		105 FT											
							TOWN TOTALS	455.0	0.0	16.0	5.0	5.0	75	0.0	0.0	83		1245.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**
FILE NAME: **Stamford.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
STAMFORD SHEET 11
PLOT DATE: **8/5/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **19** OF **198**