DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
READSBORO VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	7.138	G	VR-017	24	30		NO PARKING BETWEEN SIGNS ← LEGAL LOAD LIMIT 24,000 POUNDS						1		X												PHELPS LANE TH-22, ~~SCHOOL RD~~ NEW POST WAS DAMAGED. ON 12-9-10 THIS SIGN WAS RE-INSTALLED.			
		G	VR-017	24	30			5.00			2	2				1		X											E-141
SB	7.130	H	R1-1	30	30		PHELPS LANE STOP				1	1	1		X												PHELPS LANE TH-22, ~~SCHOOL RD~~			
		H	R1-1	30	30			6.25								1		X										X	
SB	7.126	F	S1-1YG	30	30		SCHOOL PENTAGON			1				X															
		F	W16-7YG	24	12		LEFT HAND DOWN ARROW			1																			
SB	7.080	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS SPEED LIMIT 25	5.00			1	1				1		X								SALVAGED 25 MPH SIGN ONTO NEW POST TH-23, EAST MAIN			E-141
SB	7.072	H	R1-1	30	30		GLEN AVE EAST MAIN ST				2	2	1		X												TH-23, EAST MAIN			
		H	R1-1	30	30		STOP	6.25								1		X										X	
							CLASS 1 PORTION OF HIGHWAY																							
SB	6.550	F	VR-039	24	12		STATE HIGHWAY BEGINS			1				X															
		F	R2-1	24	30		SPEED LIMIT 40			1																			
SB	6.529	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		F	S3-1	30	30			6.25								1		X										X	
SB	6.350	F	R2-1	24	30		SPEED LIMIT 50			1				X															
							SHEET TOTALS	28.75 SF	0.00 SF	5 EA	~~6~~ 0 EA	~~6~~ 0 EA	4 EA	0 EA	0 EA	5 EA	75 FT											
							TOWN TOTALS	408.4	0.0	34.0	3.0	3.0	84	0.0	2.0	64	960.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Readsboro.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
READSBORO SHEET 9

PLOT DATE: **8/5/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **30** OF **198**