DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WHITINGHAM VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.037	A	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
NB	6.113	A	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
NB	6.144	A	VW-054L	30	30			6.25								1		X						INSTALL 165 FEET NORTH OF EXISTING HIDDEN DRIVE LEFT SIGN LOCATION			E-154
NB	~~6.168~~ 6.182	A	W1-4L	30	30			6.25								1		X									125 INSTALL ~~200~~ FEET NORTH OF NEW HIDDEN DRIVE LEFT SIGN	X		
NB	6.269	A	W1-2R	30	30		RIGHT CURVE						1		X														
NB	6.291	A	S1-1YG	36	36		SCHOOL PENTAGON			1				X															
		A	W16-9YG	24	12		AHEAD			1																			
NB	6.381	C	VR-017	24	30								1		X														
		C	VR-017	24	30			5.00								1		X								TH-58, GINNY MORSE RD			E-141
		C	R2-1				SPEED LIMIT 30				1	1														REINSTALL TOWN'S SIGN BELOW NEW LEGAL LOAD SIGN			
NB	6.389	D	R1-1	30	30								1		X														
		D	R1-1	30	30		1000 1321 0639	6.25								1		X								TH-58, GINNY MORSE RD	X		
NB	6.401	A	VW-202	30	30		TRUCKS ENTERING				1	1	1		X														
NB	6.429	A	VW-202	30	30			6.25								1		X						INSTALL 150 FEET NORTH OF EXISTING TRUCKS ENTERING SIGN ASSEMBLY			E-154
NB	6.535	A	OM-3R	12	36		RIGHT OBJECT MARKER						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	30.00 SF	0.00 SF	2 EA	~~2~~ 1 EA	~~2~~ 1 EA	7 EA	0 EA	0 EA	5 EA			75 FT									
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	1058.3	0.0	40.0	13.0	13.0	220	0.0	0.0	193			2895.0									

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Whitingham.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **J. Kelly**
WHITINGHAM SHEET 11

PLOT DATE: **8/5/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **T. Guazzoni**
SHEET **47** OF **198**