DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WHITINGHAM			**VT 100**				FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W7-3A	24	18	FY		3.00																			X		
NB	7.178	A	W7-1B	36	36		HILL SYMBOL (11% GRADE)				1				X											RELOCATE SIGNS 625 FEET SOUTH AND INSTALL ON NEW POSTS			
		A	W7-2B	24	18		TRUCKS USE LOWER GEAR				1															SALVAGE TO MP 7.060			
		A	W7-3A	24	18		NEXT 1/2 MILE				1																		
NB	7.249	A	W1-2R	30	30		RIGHT CURVE						1		X														
NB	7.288	A	W3-5	36	36		SPEED REDUCTION (30)			1				X															
NB	7.319	A	VW-054R	30	30		HIDDEN DRIVE RIGHT				1	1			X	1		X								REINSTALL SIGN ON NEW POST			
NB	7.353	A	VD-018	30	18								1		X														
		A	VD-018	30	18		JACKSONVILLE WILMINGTON 7	3.75								1		X											E-128A
NB	7.408	A	R2-1	24	30		SPEED LIMIT 30						1		X														
		A	VR-020	24	30		NO PARKING ON TRAVELED LANE						1																
NB	7.414	A	R2-1	30	36		SPEED LIMIT 30	7.50								1		X								INSTALL 30 FEET NORTH OF EXISTING SPEED LIMIT 30 SIGN ASSEMBLY.		6	
NB	7.448	A	VR-020	24	30		NO PARKING ON TRAVELED LANE						1		X														
NB	7.459	A	W1-8	18	24								1		X														
		A	W1-8	18	24	FY		3.00								1		X									X		
							SHEET TOTALS	17.25	0.00	1	4	1	6	0	0	4		60										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	1058.3	0.0	40.0	13.0	13.0	220	0.0	0.0	193		2895.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**
FILE NAME: **Whitingham.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
WHITINGHAM SHEET 13
PLOT DATE: **8/5/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **T. Guazzoni**
SHEET **49** OF **198**