| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WHITINGHAM VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| SB | 5.102 | F | W1-2L | 30 | 30 | | LEFT CURVE | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | W13-1 | 18 | 18 | | 40 MPH PLAQUE | | | | | | 1 | | | | | | | | | | | | | | | |
| SB | 5.090 | G | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | G | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | TH-15, CORSE RD | | | E-141 |
| SB | 5.084 | H | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | SALVAGED STREET SIGN AND MM ONTO NEW POST. | | | |
| | | H | R1-1 | 30 | 30 | | 1000<br>1321<br>0509 | 6.25 | | | | | | | | 1 | | X | | | | | | | | TH-15, CORSE RD | X | | |
| SB | 5.056<br>~~5.065~~ | F | W1-2MbL | 30 | 30 | | | 6.25 | | | | | | | | 2 | | X | | | | | | | | INSTALL 400 FEET NORTH OF TH-~~15~~ 59, PLUMB RD. | | 6 | |
| | | F | S3-1 | 30 | 30 | |  | 6.25 | | | | | | | | | | | | | | | | | | | | | |
| SB | 4.740 | F | W3-5 | 36 | 36 | | SPEED REDUCTION (40) | | | 1 | | | | X | | | | | | | | | | | | | | | |
| SB | 4.675 | F | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| SB | 4.640 | F | VW-054R | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | VW-054R | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | | | E-154 |
| SB | 4.600 | F | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | R2-1 | 30 | 36 | | | 7.50 | | | | | | | | 1 | | X | | | | | | | | | | 6 | |
| SB | 4.549 | F | W2-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 37.50 | 0.00 | 2 | ~~0~~ | ~~0~~ | 7 | 0 | 0 | 6 | | 90 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 1058.3 | 0.0 | 40.0 | 13.0 | 13.0 | 220 | 0.0 | 0.0 | 193 | | 2895.0 | | | | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Stamford-Andover VT100
PROJECT NUMBER: STPG SIGN(20)

FILE NAME: Whitingham.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: J. Kelly
WHITINGHAM SHEET 27

PLOT DATE: 8/5/2009
DRAWN BY: I. Shea
CHECKED BY: T. Guazzoni
SHEET 63 OF 198