| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WHITINGHAM VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | F | W1-3R | 30 | 30 | | RIGHT REVERSE CURVE | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | W13-1 | 18 | 18 | | 20 MPH PLAQUE | | | | | | 1 | | | | | | | | | | | | | | | | |
| SB | 4.210 | F | S3-1 | 30 | 30 | FY | | 6.25 | | | | | | | | 2 | | X | | | | | | | | | 85 INSTALL ASSEMBLY ~~110~~ FEET SOUTH OF EXISTING AND ACROSS FROM "B" ASSEMBLY | X | | |
| | | F | W1-3R | 30 | 30 | FY | | 6.25 | | | | | | | | | | | | | | | | | | | GATE-POSTED ASSEMBLIES SHOULD BE AT SAME MILE POINT | X | | |
| | | F | W13-1 | 18 | 18 | FY | | 2.25 | | | | | | | | | | | | | | | | | | | | X | | |
| SB | 4.168 | F | W11-2YG | 30 | 30 | | PEDESTRIAN SYMBOL | | | 1 | | | | X | | | | | | | | | | | | | | | | |
| | | F | W16-4YG | 24 | 18 | | NEXT 500 FEET | | | 1 | | | | | | | | | | | | | | | | | | | | |
| SB | 4.044 | G | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | G | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | TH-17, SCHOOL ST | | | E-141 |
| | | ~~G~~ | ~~N/A~~ | | | | ~~TOWN SIGN - SLOW CHILDREN~~ | | | | | | ~~1~~ | | | | | | | | | | | | | | REMOVE ILLEGAL SIGN. RETURN TO TOWN - SIGN MISSING | | | |
| SB | 4.038 | H | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | SALVAGED STREET SIGN AND MM ONTO NEW POST | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | TH-17, SCHOOL ST | X | | |
| SB | 3.991 | G | VR-017 | 24 | 30 | | | 5.00 | | | | | 1 | | | 1 | | X | | | | | | | | | TH-11, BROOK ST | | | E-141 |
| | | ~~G~~ | ~~N/A~~ | | | | ~~SLOW CHILDREN~~ | | | | | | 1 | | | | | | | | | | | | | | ~~REMOVE ILLEGAL SIGN. RETURN TO TOWN~~ SALVAGED SPEED LIMIT SIGN ONTO NEW POST | | | |
| SB | 3.986 | H | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 31.00 SF | 0.00 SF | 2 EA | ~~2~~ 0 EA | ~~2~~ 0 EA | 7 EA | 0 EA | 0 EA | 5 EA | | | 75 FT | | | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 1058.3 | 0.0 | 40.0 | 13.0 | 13.0 | 220 | 0.0 | 0.0 | 193 | | | 2895.0 | | | | | | | | | | |

PROJECT NAME: Stamford-Andover VT100
PROJECT NUMBER: STPG SIGN(20)

FILE NAME: Whitingham.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: J. Kelly
WHITINGHAM SHEET 29

PLOT DATE: 8/5/2009
DRAWN BY: I. Shea
CHECKED BY: T. Guazzoni
SHEET 65 OF 198