DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WHITINGHAM VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	3.063	G	VR-017	24	30								1		X														
		G	VR-017	24	30			5.00								1		X								TH-56, DAM RD			E-141
SB	3.058	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25							1		X								TH-56, DAM RD	X		
SB	2.932	G	VR-017	24	30			5.00								1		X								TH-32, PIKE RD			
SB	2.927	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25								1		X								TH-32, PIKE RD	X		
SB	2.575	F	N/A				EMPTY POST								X											AT THE REQUEST OF AOT-DIST #1, THIS SIGN WAS REMOVED AND RE-INTALLED FARTHER AWAY FROM THE DITCHLINE.			
		F	W1-4L	30	30			6.25				I	I			1		X									X		
SB	2.309	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
SB	2.275	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
		F	W1-4R	30	30			6.25								1		X									X		
		F	W13-1	18	18			2.25																			X		
SB	2.237	F	VW-054R	30	30			6.25								1		X								INSTALL 200 FEET SOUTH OF EXISTING HIDDEN DRIVE RIGHT SIGN			E-154
SB	~~2.130~~ 2.211	F	S3-1	30	30		SCHOOL BUS STOP AHEAD	6.25					1		X											SCHOOL BUS STOPS AT THIS LOCATION. OLD SIGN REMOVED, NEW SIGN INSTALLED.			
							SHEET TOTALS	~~43.50~~ 49.75 SF	0.00 SF	0 EA	~~0~~ EA	~~0~~ EA	6 EA	0 EA	0 EA	7 EA		105 FT							
							TOWN TOTALS	1058.3	0.0	40.0	13.0	13.0	220	0.0	0.0	193		2895.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Whitingham.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
WHITINGHAM SHEET 31

PLOT DATE: **8/5/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **T. Guazzoni**
SHEET **67** OF **198**