

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WILMINGTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
NB	0.000	C	VD-024	60	7.5																		AT THE REQUEST OF AOT-DIST. *1 THIS SET OF SIGNS WAS MOVED OUT OF THE DITCHLINE.	TOWN LINE SIGN IS MISSING. EMPTY POST IS 171 FT ± SOUTH OF THE JCT WITH HEBARD RD (TH-39).					
		C	VD-024	72	10			5.00											X					INSTALL IN SAME POSITION AS EMPTY POST REMOVAL, IN "C" POSITION.		4			
		C	VD-700	6	10			0.42																WILMINGTON MILE MARKER. INSTALL ON LEFT POST UNDER WILMINGTON.			E-138		
		C	VD-700	6	10			0.42																WHITINGHAM MILE MARKER. INSTALL ON RIGHT POST UNDER WHITINGHAM..			E-138		
NB	0.032	C	VR-017	24	30			5.00																	HEBAR D HILL RD (TH-39)			E-141	
NB	0.040	D	R1-1	24	24																								
		D	R1-1	30	30			6.25																	HEBAR D HILL RD (TH-39)	X			
NB	0.345	A	W1-2L	30	30			6.25																* SEE NOTE ON SHEET #76	INSTALL BEHIND GUARD RAIL, 315 FT ± SOUTH OF THE GRAVEL ROAD TO BE REOPENED (SEE NEXT 2 ENTRIES)	X			
NB	0.394	C	VR-017	24	30			5.00																	RADER RD (TH-70). THIS CLASS III ROAD TO BE REOPENED (EDGE LINE AND CENTERLINE MAY STILL BE CLOSED)			E-141	
NB	0.400	D	R1-1	30	30			6.25																	RADER RD (TH-70); GRAVEL ROAD w/ A GUARDRAIL BREAK, JUST BEYOND LEFT CURVE BEGIN / ON SLIGHT UPHILL	X			
NB	0.638	C	VR-017	24	30			5.00																	(TH-36)			E-141	
NB	0.644	D	R1-1	30	30			6.25																	(TH-36)	X			
NB	0.941	C	VR-017	24	24																				RADER ROAD (TH-69), SOUTHERLY APPROACH.				
		C	VR-017	24	30			5.00																	INSTALL AT A POINT ON TH-69 JUST BEYOND THE CONVERGANCE OF THE TWO APPROACHES.			E-141	
NB	0.949	D	R1-1	24	24																			RADER ROAD (TH-69), SOUTHERLY APPROACH.					
SIGN SUMMARY SHEET							SHEET TOTALS	57.09 50.84	0.00	0	3	3	7	0	0	10	150							PROJECT NAME: Stamford-Andover VT100					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN(20)					
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	825.4	0.0	64.0	15.0	15.0	145	0.0	0.0	145	2175.0							FILE NAME: Wilmington.xls	PLOT DATE: 8/6/2009				
																							PROJECT MANAGER: N. Avery	DRAWN BY: T. Guazzoni					
																							DESIGNED BY: M. Miller	CHECKED BY: T. Guazzoni					
																							WILMINGTON SHEET 1	SHEET 71	OF 198				