DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILMINGTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W13-1	24	24	FY		4.00																		NOTE UPSIZED ADVISORY SPEED PLAQUE.	X		
NB	1.777	A	W1-4R	30	30		REVERSE CURVE RIGHT						1		X													
		A	W13-1	18	18		35 MPH (PLAQUE)						1															
NB	1.980	A	VW-168L	30	30		HIDDEN SIDE ROAD LEFT (TEXT)						1		X													
NB	2.000	A	VW-054L	30	30			6.25								1		X							INSTALL 100 FT ± NORTH OF THE HIDDEN SIDE ROAD SIGN THAT WAS JUST REMOVED.			E-154
NB	2.155	A	VD-062BC	74.75	16		TRAVEL INFO SYMBOLS			1				X														
		A	VD-062C	74.75	16		TRAVEL INFO			1																		
NB	2.180	A	VW-544	36	36								1		X													
		A	VW-544	36	36			9.00								2		X								E-154
NB	2.275	A	W11-2	30	30		PEDESTRIAN SYMBOL			1				X														
		A	W16-9P	24	12	FYG		2.00																		ADD THE "AHEAD" PLAQUE UNDER THE PED SIGN	X		
NB	2.310	A	W3-1	36	36		STOP AHEAD			1				X														
NB	2.348	A	M2-1	21	15		JCT			1				X														
		A	M1-5	24	24		VERMONT ROUTE 9			1				X														
NB	2.391	A	D1-1A	72	12		<--- WILMINGTON 1			1				X														
							SHEET TOTALS	21.25 SF	0.00 SF	7 EA	0 EA	0 EA	4 EA	0 EA	0 EA	3 EA	45 FT											
							TOWN TOTALS	825.4	0.0	64.0	15.0	15.0	145	0.0	0.0	145	2175.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wilmington.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
WILMINGTON SHEET 3

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **73** OF **198**