





DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WILMINGTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
SB	2.469	E	R1-1	30	30		STOP			1				X								RETAIN THE "GATEPOSTED" LEFT-SIDE 30" STOP SIGN FOR NB VT-100.							
SB	2.429	F	M3-3	24	12		SOUTH			1				X															
		F	M1-5	30	24		VERMONT ROUTE 100			1																			
SB	2.392	F	R2-1	24	30		SPEED LIMIT 50			1				X															
SB	2.354	F	D2-1	72	12		JACKSONVILLE 6			1				X															
		F	D2-1	72	12		WHITINGHAM 9			1																			
SB	2.319	F	W11-1	30	30	FYG	BICYCLE SYMBOL			1				X															
		F	W16-1	24	30	FYG	SHARE THE ROAD (TEXT)			1																			
SB	2.210	F	VW-168R	30	30		HIDDEN SIDE ROAD RIGHT							1															
SB	2.160	F	VW-054R	30	30			6.25							1		X					*SEE NOTE ON NEXT SHEET	INSTALL 260 FT ± SOUTH OF EXISTING HIDDEN SIDE ROAD SIGN BEHIND GUARD RAIL.			E-154			
SB	1.925	F	W1-6	48	24			8.00							2		X					INSTALL 175 FT IN ADVANCE OF EXISTING (NORTH OF) THE LARGE ARROW/CLUSTER FACING NB TRAFFIC, AT M.P. 1.890.	X						
SB	1.923	E	W1-6	48	24			8.00							2		X					INSTALL FACING NB TRAFFIC, 5 FT ± SOUTH OF THE SB FACING ARROW. MAINTAIN 10 FT MIN TO POLE.	X						
SB	1.892	F	W1-6	48	24			8.00							2		X					INSTALL FACING SB TRAFFIC, 10 FT NORTH OF THE NB FACING ARROW (WHICH WILL BE REPLACED).	X						
SB	1.890	E	W1-6	48	24									1															
		E	OM1-1	18	18		OBJECT MARKER							1															
SIGN SUMMARY SHEET							SHEET TOTALS	36.50 30.25	0.00	8	0	0	3	0	0	7	105						PROJECT NAME: Stamford-Andover VT100						
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	825.4	0.0	64.0	15.0	15.0	145	0.0	0.0	145	2175.0						PROJECT NUMBER: STPG SIGN(20)	FILE NAME: Wilmington.xls	PLOT DATE: 8/6/2009				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT						PROJECT MANAGER: N. Avery	DRAWN BY: T. Guazzoni					
																							DESIGNED BY: M. Miller	CHECKED BY: T. Guazzoni					
																							WILMINGTON SHEET 5	SHEET 75 OF 198					