DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILMINGTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	D2-1	72	12			6.00																				5	
NB	2.715	A	W1-3R	30	30		RIGHT REVERSE TURN SYMBOL						1		X														
NB	2.758	A	R2-1	24	30		SPEED LIMIT 25			1				X															
NB	2.780	A	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
NB	2.785	A	W1-3R	30	30			6.25								1		X									INSTALL 25 FT ± NORTH OF HIDDEN DRIVE RIGHT SIGN JUST-REMOVED.	X	
NB	2.830	A	OM-3R	12	36			3.00								1											INSTALL 250 FT ± NORTH OF HIDDEN DRIVE RIGHT SIGN JUST-REMOVED.	X	
NB	2.832	A	N/A				EMPTY POST								X														
NB	2.903	A	R2-1	24	30		SPEED LIMIT 25			1				X															
NB	2.987	C	VR-017	24	30								1		X												STOWE HILL RD (TH-21)		
		C	VR-017	24	30			5.00								1		X											E-141
NB	2.995	D	R1-1	30	30								1		X												STOWE HILL RD (TH-21)		
		D	R1-1	30	30		1000 1322 0299	6.25								1		X										X	
NB	3.080	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X										X	
NB	3.233	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 LBS			1				X												ADAMS DR (TH-22)			
							SHEET TOTALS	31.50	0.00	3	0	0	5	0	0	~~4~~ 5		60								
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT								
							TOWN TOTALS	825.4	0.0	64.0	15.0	15.0	145	0.0	0.0	145		2175.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wilmington.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
WILMINGTON SHEET 8

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **78** OF **198**