DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILMINGTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		H	R1-1	36	36			9.00			I	I				2		X		SALVAGED STREET SIGN ONTO NEW POST.					INSTALL THE UPSIZED STOP SIGN ON TWO NEW POSTS.	X		
SB	4.975	K	R4-7	24	38								1		X											SEE NOTE FOR NB MM 4.860 - PAGE 80			
		K	OM1-1	18	18								1															
		J	OM1-1	18	18								1															
		K	R4-7	24	~~38~~ 30			5.00								1		X							INSTALLED IN THE RAISED MEDIAN ACROSS FROM ± THE TH-1 RIGHT-SIDE STOP SIGN.	X		
		K	OM1-1	18	18			2.25																	INSTALL OBJECT MARKERS BACK-TO-BACK.	X		
		J	OM1-1	18	18			2.25																	PROVIDE 4 FT CLEARANCE TO OBJECT MARKERS.	X		
SB	4.930	F	M3-3	24	12			2.00					I			1		X							GREEN ON WHITE SHEETING. INSTALL 250 FT SOUTH OF JCT w/ COLDBROOK RD (TH-1)	X		
		F	M1-5	30	24			5.00					I															E-136B
SB	4.618	F	W3-5	36	36		SPEED REDUCTION 40 MPH AHEAD (SYMBOL)			1				X															
SB	4.522	F	R2-1	24	30		SPEED LIMIT 40						1		X														
		F	R2-1	30	36			7.50								1		X										6	
SB	4.480	F	W1-2R	30	30								1		X														
		F	W1-2R	30	30			6.25								1		X									X		
SB	4.400	F	S1-1YG	36	36		PENTAGONAL SCHOOL SYMBOL			1				X															
							SHEET TOTALS	39.25 SF	0.00 SF	2 EA	~~0~~ 1 EA	~~0~~ 1 EA	~~5~~ 7 EA	0 EA	0 EA	6 EA		90 FT										
							TOWN TOTALS	825.4	0.0	64.0	15.0	15.0	145	0.0	0.0	145		2175.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wilminaton.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
WILMINGTON SHEET 21

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **91** OF **198**