| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WILMINGTON VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | F | W16-9YG | 36 | 20 | | AHEAD (PLAQUE) | | | 1 | | | | | | | | | | | | | | | | | | |
| SB | 4.351 | F | R2-1 | 24 | 30 | | SPEED LIMIT 40 | | | 1 | | | | X | | | | | | | | | | | | | | |
| SB | 4.236 | H | R1-1 | 30 | 30 | | STOP | | | 1 | | | | X | | | | | | | | | | | | SCHOOL DRIVEWAY ~ PRIVATE STOP SIGN. | | | |
| SB | 4.232 | F | R8-3A | 24 | 24 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | VR-644P | 24 | 12 | | BEGIN | | | | | | 1 | | | | | | | | | | | | | | | |
| | | F | R8-3A | 24 | 24 | | | 4.00 | | | | | | | | 1 | | X | | | | | | | | X | | |
| | | F | M4-11 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | | RED ON WHITE SHEETING | | | E-140 |
| SB | 4.215 | F | W1-2L | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | W13-1 | 18 | 18 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | F | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | X | | |
| | | F | W13-1 | 18 | 18 | | | 2.25 | | | | | | | | | | | | | | | | | | X | | |
| SB | 4.180 | F | R8-3A | 24 | 24 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | R8-3A | 24 | 24 | | | 4.00 | | | | | | | | 1 | | X | | | | | | | | X | | |
| SB | 4.152 | F | R8-3A | 24 | 24 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | M4-6P | 24 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 18.50 SF | 0.00 SF | 3 EA | 0 EA | 0 EA | 7 EA | 0 EA | 0 EA | 3 EA | 45 FT | | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 825.4 | 0.0 | 64.0 | 15.0 | 15.0 | 145 | 0.0 | 0.0 | 145 | 2175.0 | | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**
FILE NAME: **Wilmington.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
WILMINGTON SHEET 22
PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **92** OF **198**