| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WILMINGTON VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | F | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | D1-1A | 72 | 12 | | MARLBORO 11 | 6.00 | | | | | | | | 2 | | | X | | | | | | | | | 5 | |
| | | F | D1-1A | 72 | 12 | | BRATTLEBORO 19 | 6.00 | | | | | | | | | | | | | | | | | | | | 5 | |
| | | F | D1-1A | 72 | 12 | | SEARSBURG 7 | 6.00 | | | | | | | | | | | | | | | | | | | | 5 | |
| | | F | D1-1A | 72 | 12 | | BENNINGTON 21 | 6.00 | | | | | | | | | | | | | | | | | | | | 5 | |
| SB | 2.720 | F | W1-3R | 30 | 30 | | RIGHT REVERSE TURN | | | | | | 1 | | X | | | | | | | | | | | | | | |
| SB | 2.630 | F | VR-020 | 24 | 30 | | NO PARKING ON TRAVELED LANE | | | | | | I | | | | | | | | | | | | | | OLD SIGN WAS REMOVED. | | |
| | | F | VR-020 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | | E-146 |
| SB | 2.570 | F | M3-2 | 24 | 12 | | EAST | | | | 1 | 1 | | ~~X~~ | X | 2 | | | X | | | | | | | | RETAIN FRAME | | |
| | | F | M1-5 | 24 | 24 | | VERMONT 9 | | | | 1 | 1 | | | | | | | | | | | | | | AS PER J. KELLY, TRAFFIC OPS, THE OLD TUBULAR POSTS WERE REMOVED AND NEW SQUARE STEEL POSTS WERE INSTALLED. | | | |
| | | F | M6-1 | 21 | 15 | | <--- LEFT | | | | 1 | 1 | | | | | | | | | | | | | | | | | |
| | | F | M3-3 | 24 | 12 | | SOUTH | | | | 1 | 1 | | | | | | | | | | | | | | | | | |
| | | F | M1-5 | 30 | 24 | | VERMONT 100 | | | | 1 | 1 | | | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 29.00 SF | 0.00 SF | 0 EA | 5 EA | 5 EA | 4 EA | 0 EA | 0 EA | ~~4~~ 5 EA | | 75 FT | | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 825.4 | 0.0 | 64.0 | 15.0 | 15.0 | 145 | 0.0 | 0.0 | 145 | | 2175.0 | | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Stamford-Andover VT100
PROJECT NUMBER: STPG SIGN(20)

FILE NAME: Wilmington.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: M. Miller
WILMINGTON SHEET 26

PLOT DATE: 8/6/2009
DRAWN BY: T. Guazzoni
CHECKED BY: T. Guazzoni
SHEET 96 OF 198