DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
DOVER VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	M1-5	24	24								1																
		A	M3-1	24	12		NORTH / VERMONT 100	2.00								1		X								GREEN ON WHITE SHEETING	X		
		A	M1-5	30	24		SPEED LIMIT 50	5.00																					E-136B
NB	4.190	A	R2-1	24	30			5.00								1		X								INSTALL 240 FT ± NORTH OF THE ROUTE MARKER ASSEMBLY	X		
NB	4.821	C	VR-017	24	30		NO PARKING / LEGAL LOAD LIMIT 24,000 POUNDS				I	I	1		X					ORDINANCE SIGN SALVAGED ONTO NEW POST.						AHMEEK RD (TH-13)			
		C	VR-017	24	30			5.00					I			1		X											E-141
NB	4.829	D	R1-1	30	30		STOP						1		X											AHMEEK RD (TH-13)			
		D	R1-1	30	30			6.25								1		X									X		
NB	5.270	A	W11-6H	30	30		SNOWMOBILE SYMBOL			I			~~1~~		X											SNOWMOBILES USE THE CROSSING. NO WORK WAS DONE.			
NB	5.300	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS / NO PARKING				I	I	1		X					ORDINANCE SIGN SALVAGED ONTO NEW POST.						BLUE BROOK RD (TH-8)			
		C	VR-017	24	30			5.00					I			1		X											E-141
NB	5.308	D	R1-1	30	30		STOP / BLUE BROOK RD				I	I	1		X											BLUE BROOK RD (TH-8)			
		D	R1-1	30	30		1000 1304 0530	6.25								1		X								STREET SIGN AND MMSALVAGED ONTO NEW POST.	X		
NB	5.453	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											DUNCAN RD (TH-33)			
		C	VR-017	24	30			5.00								1		X											E-141
SIGN SUMMARY SHEET							SHEET TOTALS	39.50	0.00	~~1~~ 0	~~3~~ 0	~~3~~ 0	~~8~~ 7	0	0	7		105										
VERMONT AGENCY OF TRANSPORTATION								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	648.1	0.0	30.0	3.0	1.0	116	0.0	0.0	112		1680.0										

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Dover.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
DOVER SHEET 10

PLOT DATE: **8/6/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **T. Guazzoni**