DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STRATTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.620	A	VW-054	30	30								1		X													
		A	VW-054L	30	30			6.25								1		X										E-154
SB	1.064	G	R2-1				SPEED LIMIT 25 (TOWN)				1	1														REINSTALL SIGN BELOW NEW LEGAL LOAD SIGN			
		G	VR-017	24	30								1		X						STREET SIGN AND MM SALVAGED ONTO NEW POST.						TH-20, PENNY AVE			
		G	VR-017	24	30			5.00								1		X										E-141
SB	1.060	H	R1-1	30	30								1		X												TH-20, PENNY AVE			
		H	R1-1	30	30			6.25								1		X									X		
SB	0.600	F	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
		F	W13-1	18	18		40 MPH PLAQUE						1																
SB	0.549	F	W7-1	30	30		HILL SYMBOL						1		X														
		F	W7-2b	24	18		TRUCKS USE LOWER GEAR						1																
		F	W1-4L	30	30			6.25								1		X									X	
		F	W13-1	18	18			2.25																			X	
SB	0.511	F	W7-1	30	30			6.25								1		X									X	
NB	1.325	A	VW-054R	30	30			6.25								1											300 INSTALL ~~200~~ FEET SOUTH OF EXISTING HILL SYMBOL SIGN ASSEMBLY			
																											NEW SIGN INSTALLED PER REQUEST OF M. MILLER, TRAFFIC OPS. SEE EMAIL DATED 5-7-10			
							SHEET TOTALS	38.50 ~~32.25~~ SF	0.00 SF	0 EA	1 EA	1 EA	7 EA	0 EA	0 EA	6 ~~5~~ EA		75 FT								
							TOWN TOTALS	53.1	0.0	0.0	3.0	3.0	12	0.0	0.0	10		150.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Stratton.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
STRATTON SHEET 2

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **118** OF **198**