| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WARDSBORO VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | A | W1-6 | 60 | 30 | FY | | 12.50 | | | | | | | | 2 | | X | | | | | | | | | X | | |
| NB | 2.310 | A | OM-3R | 12 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | OM-3R | 12 | 36 | | | 3.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.325 | B | OM-3L | 12 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | B | OM-3L | 12 | 36 | | | 3.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.390 | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.555 | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.785<br>~~2.765~~ | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | MOVED 100' N. OF ORGINAL LOCATION FOR BETTER VISIBILITY. | | | |
| | | A | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.800 | A | M3-3 | 24 | 12 | | | 2.00 | | | | | | | | 1 | | X | | | | | | | | | GREEN ON WHITE SHEETING. INSTALL 50 FT +/- SOUTH OF END OF GUARD RAIL | X | | |
| | | A | M1-5 | 30 | 24 | | | 5.00 | | | | | | | | | | | | | | | | | | | | | E-136B |
| NB | 3.802 | C | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | TH-6, LOWER PODUNK RD | | | |
| | | C | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | | E-141 |
| | | | | | | | SHEET TOTALS | 45.50 SF | 0.00 SF | 0 EA | 0 EA | 0 EA | 6 EA | 0 EA | 0 EA | 9 EA | | 135 FT | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 633.3 | 0.0 | 24.0 | 12.0 | 12.0 | 108 | 0.0 | 0.0 | 129 | | 1935.0 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wardsboro.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **J. Kelly**
WARDSBORO SHEET 5

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **123** OF **198**