DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WARDSBORO VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.584	C	W1-6	48	24	~~FY~~		8.00								2		X								ARROW FACES NB TRAFFIC, BUT I**NSTALL PARALLEL TO VT-100**; BEHIND RAIL 10 FT± NORTH OF STOP SIGN.	X		
NB	6.596	A	M3-1	24	12		NORTH			1				X														
		A	M1-5	30	24		VERMONT 100			1																		
NB	6.675	A	R2-1	24	30								1		X													
		A	R2-1	24	30			5.00								1		X									X	
NB	6.880	A	R2-1	24	30		SPEED LIMIT 40			1				X														
NB	6.960	A	S1-1YG	36	36		SCHOOL PENTAGON			1				X														
		A	W16-9YG	24	10		AHEAD			1																		
NB	7.093	A	D1-2L	72	20		<--- WARDSBORO ELEMENTARY SCHOOL			1				X														
		B	D1-2R	72	20		WARDSBORO ELEMENTARY SCHOOL --->			1																		
NB	7.280	A	R2-1	24	30		SPEED LIMIT 50			1				X														
SB	7.280	F	R2-1	24	30		SPEED LIMIT 40			1				X														
SB	7.215	F	S1-1YG	36	36		SCHOOL PENTAGON			1				X														
		F	W16-9YG	24	10		AHEAD			1																		
SB	7.095	G	VR-017	24	30								2 ~~1~~		X											SALVAGED SEAT BELT SIGN ONTO NEW POST TH-45, SCHOOL ~~DR~~RD			
							SHEET TOTALS	13.00 SF	0.00 SF	11 EA	~~0~~ EA	~~0~~ EA	3 ~~2~~ EA	0 EA	0 EA	3 EA													
							TOWN TOTALS	633.3	0.0	24.0	12.0	12.0	108	0.0	0.0	129			1935.0 FT									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wardsboro.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **J. Kelly**
WARDSBORO SHEET 10

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **128** OF **198**