DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WARDSBORO VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	6.534	F	R2-1	24	30		SPEED LIMIT 35						1		X														
SB	6.527	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 LBS						1		X												TH-5, MAIN ST			
		G	R2-1	24	30		SPEED LIMIT 25 (TOWN INSTALLED)				1	1	I													INSTALL UNDER NEW LEGAL LOAD LIMIT 24,000 LBS			
		H	R1-1	30	30		LEGAL LOAD LIMIT 24,000 POUNDS						1																
		G	VR-017	24	30			5.00								1		X								INSTALL LEGAL LOAD LIMIT AND STOP SIGNS BACK-TO-BACK			E-141
		H	R1-1	30	30		STOP	6.25					I														X		
SB	6.522	H	R1-1	30	30		STOP MAIN ST						1		X												TH-5, MAIN ST			
		H	R1-1	30	30			6.25								1		X									SALAVGED STREET SIGN ONTO NEW POST	X		
SB	6.510	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X									TH-14, FORNUTO RD			E-141
SB	6.500	H	R1-1	30	30		STOP						1		X														
		H	R1-1	30	30			6.25								1		X									TH-14, FORNUTO RD	X		
SB	~~6.462~~ 6.442	F	M3-3	24	12		SOUTH VERMONT 100	2.00								1		X									GREEN ON WHITE SHEETING.	X		
		F	M1-5	30	24			5.00																			INSTALL ASSEMBLY ~~200~~ 300 FT± SOUTH OF FORNUTO RD, JUST SOUTH OF THE DRIVEWAY			E-136B
SB	6.400	F	R2-1	24	30		SPEED LIMIT 35						1		X														
		F	R2-1	24	30			5.00								1		X										X		
							SHEET TOTALS	40.75	0.00	0	1	1	~~8~~ 6	0	0	6		90											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	633.3	0.0	24.0	12.0	12.0	108	0.0	0.0	129		1935.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Wardsboro.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
WARDSBORO SHEET 12

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **130** OF **198**