DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
LONDONDERRY VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	VD-062C	72	16		BUSINESS SIGN			1																			
SB	6.150	F	W1-10L	30	30		LEFT CURVE WITH RH SIDE ROAD						1		X														
		F	W13-1	18	18		40 MPH PLAQUE						1																
SB	6.115	F	S3-1	30	30								1		X														
		F	W1-10L	30	30			6.25								2		X									X	
		F	S3-1	30	30			6.25																			INSTALL SCHOOL BUS STOP AHEAD SIGN BELOW LEFT CURVE SIGN	X	
SB	6.080	F	~~W3-5~~ R2-1	~~36~~ 30	36		SPEED ~~REDUCTION~~ LIMIT (30)			1				X													SPEED LIMIT SIGN CHANGE. SEE SHEET #151		
SB	6.039	F	W1-6	48	24		LEFT LARGE ARROW			1				X															
SB	5.998	G	VR-017	24	30								1		X												TH-63, WILLIAMS ST		
		G	VR-017	24	30			5.00								1		X											E-141
SB	5.993	H	R1-1	30	30								1		X												TH-63, WILLIAMS ST		
		H	R1-1	30	30		1000 1310 0600	6.25								1		X										X	
SB	5.975	F	W3-1	36	36		STOP AHEAD			1				X															
SB	5.965	F	R2-1	24	30					~~1~~			~~1~~	X	~~X~~												SPEED LIMIT SIGN CHANGE. SEE SHEET #151.		
		F	R2-1	24 30	30 36			~~7.50~~								~~1~~		~~X~~										6	
SIGN SUMMARY SHEET							SHEET TOTALS	~~31.25~~ 23.75 SF	0.00 SF	4 EA	0 EA	0 EA	~~6~~ 5 EA	0 EA	0 EA	5 EA		75 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	729.7	0.0	22.0	4.0	4.0	151	0.0	0.0	118		1770.0										

PROJECT NAME: Stamford-Andover VT100
PROJECT NUMBER: STPG SIGN(20)

FILE NAME: Londonderry.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: J. Kelly
LONDONDERRY SHEET 13

PLOT DATE: 8/6/2009
DRAWN BY: T. Guazzoni
CHECKED BY: T. Guazzoni
SHEET 162 OF 198