| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WESTON VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 0.000 | C | VD-024 | 60 | 7.5 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | C | VD-025 | 60 | 7.5 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | C | VD-024 | 72 | 10 | | | 5.00 | | | | | | | | 2 | | X | | | | | | | | | 4 | |
| | | C | VD-025 | 72 | 10 | | | 5.00 | | | | | | | | | | | | | | | | | | | 4 | |
| | | C | VD-700 | 6 | 10 | | | 0.42 | | | | | | | | | | | | | | | | | | INSTALL BELOW WESTON | | | E-138 |
| | | C | VD-700 | 6 | 10 | | | 0.42 | | | | | | | | | | | | | | | | | | INSTALL BELOW LONDONDERRY | | | E-138 |
| NB | 0.195 | A | W1-1MR | 30 | 30 | | RIGHT TURN WITH ANGLED CROSSROADS | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | W13-1 | 18 | 18 | | 30 MPH PLAQUE | | | | | | 1 | | | | | | | | | | | | | | | | |
| NB | 0.240 | A | VW-202 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | VW-202 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | | E-154 |
| NB | 0.278 | A | W1-1MeR | 30 | 30 | FY | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL 200 FEET NORTH OF TRUCKS ENTERING ASSEMBLY | | 7 | |
| | | A | W13-1 | 18 | 18 | FY | | 2.25 | | | | | | | | | | | | | | | | | | | X | |
| NB | 0.320 | C | VR-017 | 24 | 24 | | | | | | | | 1 | | X | | | | | | | | | | | | TH-48, LONGLEY LOOP | | | |
| | | C | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | E-141 |
| NB | 0.360 | D | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | TH-48, LONGLEY LOOP | | | |
| | | | | | | | SHEET TOTALS | 30.59 | 0.00 | 0 | 0 | 0 | 7 | 0 | 0 | 5 | | 75 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 774.4 | 0.0 | 26.0 | 12.0 | 12.0 | 139 | 0.0 | 0.0 | 140 | | 2100.0 | | | | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Weston.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
WESTON SHEET 1

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **172** OF **198**