DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WESTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		G	VR-052L	24	30			5.00								1		X									7	
SB	2.995	G	VR-052R	24	30		NO PARKING (RIGHT ARROW)				1				X											RELOCATE SIGN ~~80 FEET NORTH AND IN LINE WITH WESTON INN SIGN.~~ 150 FEET SOUTH REMOVE MM			
SB	~~2.980~~ 2.967	G	VR-052R	24	30		NO PARKING (RIGHT ARROW)					1			X	1		X										
SB	2.954	G	VR-017	24	24								1		X												TH-40, MILL LANE			
		G	VR-017	24	30			5.00								1		X											E-141
SB	2.948	H	R1-1	30	30								1		X												TH-40, MILL LANE			
		H	R1-1	30	30		1000 1421 0295	6.25								1		X										X	
SB	2.900	F	R2-1	24	30			5.00								1		X									INSTALL 250 FEET NORTH OF EXISTING AT EDGE OF PAVED SHOULDER	X		
SB	2.850	F	R2-1	24	30		SPEED LIMIT 40						1		X														
SB	2.730	F	M3-3S	24	12		SOUTH				1	1			X	1		X											
SB	2.730	F	M1-5	30	24		VERMONT 100				1	1																	
SB	2.668	F	R2-1	24	30			5.00								1		X									INSTALL 40 FEET NORTH OF EXISTING SPEED LIMIT 50 SIGN AND ACROSS FROM NB SL 40	X		
SB	2.660	F	R2-1	24	30		SPEED LIMIT 50						1		X														
SB	2.205	F	VD-062B	72	16		BUSINESS SIGN			1				X															
SB	1.170	F	W1-2R	30	30								1		X														
							SHEET TOTALS	26.25	0.00	1	~~4~~ 3	~~4~~ 3	5	0	0	7		105											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	774.4	0.0	26.0	12.0	12.0	139	0.0	0.0	140		2100.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Weston.xls** PLOT DATE: **8/6/2009**
PROJECT MANAGER: **N. Averv** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **J. Kelly** CHECKED BY: **T. Guazzoni**
WESTON SHEET 20 SHEET **191** OF **198**