DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WESTON VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W13-1	18	18								1																
		F	W1-2R	30	30			6.25								1		X									X		
		F	W13-1	18	18			2.25																			X		
SB	1.035	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	0.997	F	VW-054R	30	30			6.25								1		X								INSTALL 200 FEET SOUTH OF EXISTING HIDDEN DRIVE RIGHT SIGN AT M.P. 1.035			E-154
SB	0.935	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	0.827	F	W1-2R	30	30		RIGHT CURVE						1		X														
SB	0.750	F	W1-10R	30	30			6.25								1		X								INSTALL 400 FEET SOUTH OF EXISTING RIGHT CURVE SIGN	X		
SB	0.625	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	0.565	F	VW-054R	30	30			6.25								1		X								INSTALL AT SOUTH ABUTMENT OF BRIDGE #92			E-154
SB	0.537	F	VW-081L	30	30		TRUCKS ENTERING						1		X														
SB	0.500	F	VW-081L	30	30			6.25								1		X								INSTALL BETWEEN YELLOW HOUSE AND WHITE HOUSE (200 FEET SOUTH OF EXISTING LOCATION)			E-154
SB	0.460	F	W1-1ML	30	30		LEFT TURN WITH CROSSROADS						1		X														
		F	W13-1	18	18		30 MPH PLAQUE						1																
SB	0.435	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
							SHEET TOTALS	33.50	0.00	0	0	0	9	0	0	5		75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	774.4	0.0	26.0	12.0	12.0	139	0.0	0.0	140		2100.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Stamford-Andover VT100**
PROJECT NUMBER: **STPG SIGN(20)**

FILE NAME: **Weston.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
WESTON SHEET 21

PLOT DATE: **8/6/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **T. Guazzoni**
SHEET **192** OF **198**