

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									28	28		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
									500	500		HR	FLAGGERS	630.15				
									1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
									1	1		LS	TRAFFIC CONTROL	641.10				
									2316.2	2316.2		SF	TRAFFIC SIGNS, TYPE A	675.20				
									6255	6255		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
									472	472		EACH	REMOVING SIGNS	675.50				
									24	24		EACH	ERECTING SALVAGED SIGNS	675.60				