| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **DERBY VT 105** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| WB | 3.282 | H | R1-1 | 24 | 24 | | | | | | 2 | | 1 | | X | | | | | | | | | | | HAYWARD RD (TH-50) | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | 2 | | | | 1 | | 13.5<br>X | | | | | | | | X | | |
| WB | 2.940 | F | VW-054R | 30 | 30 | | HIDDEN DRIVE RIGHT | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| WB | 2.883 | F | VW-054R | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 16<br>X | | | | | | | | INSTALL 300 FT ± WEST OF PREVIOUS LOCATION | | | E-154 |
| WB | 2.800 | F | VW-219 | 30 | 30 | | SUMMER CAMP AREA | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 2.780 | F | VW-219 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 17<br>X | | | | | | | | INSTALL 100 FT ± WEST OF PREVIOUS LOCATION | | 6 | |
| WB | 2.405 | F | S3-1 | 30 | 30 | | SCHOOL BUS STOP AHEAD | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 2.365 | F | W1-2L | 30 | 30 | | CURVE LEFT | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | W13-1 | 18 | 18 | | 35 MPH (PLAQUE) | | | | | | 1 | | | | | | | | | | | | | | | | |
| WB | 2.285 | F | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 15<br>X | | | | | | | | INSTALL 425 FT ± WEST OF PREVIOUS LOCATION. ADVISORY SPEED BEING ELIMINATED. | X | | |
| WB | 1.560 | F | R2-5A | 24 | 30 | | REDUCED SPEED AHEAD | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 1.490 | F | VD-018 | 30 | 18 | | DERBY CENTER NEWPORT 4 | | | | | | 1 | | X | | | | | | | | | | | | VILLAGE SIGN TO BE REPLACED FURTHER AHEAD | | | |
| | | F | W3-5 | 36 | 36 | | | 9.00 | | | | | | | | 2 | | 16<br>16.3<br>X | | | | | | | | | X | | |
| WB | 1.452 | F | n/a | n/a | n/a | | (2) EMPTY POSTS | | | | | | | | X | | | | | | | | | | | | REMOVE THE TWO EMPTY POSTS | | | |
| WB | 1.400 | F | R2-1 | 24 | 30 | | | | | | | | | | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 34.00 | 0.00 | 0 | ~~0~~ 2 | ~~0~~ 2 | 8 | 0 | 0 | 6 | | ~~90~~ 93.8 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 421.4 | 0.0 | 7.0 | 1.0 | 1.0 | 90 | 0.0 | 0.0 | 62 | | 930.0 | | | | | | | | | | |

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**

FILE NAME: **Derbv.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
DERBY SHEET 8

PLOT DATE: **6/11/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **15** OF **79**