DIR	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHARLESTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	5.390	A	W2-1Mb	30	30								1		X														
		A	W2-1Mb	30	30			6.25								1		15 X										6	
EB	5.450	A	D1-1E	72	20		CHARLESTOWN ELEMENTARY SCHOOL --->			1				X															
EB	5.481	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS			1				X													CENTER SCHOOL ROAD (TH-29)			
EB	5.489	D	R1-1	30	30		STOP			1				X													CENTER SCHOOL ROAD (TH-29)			
EB	5.508	A	M3-2	24	12			2.00								1		13.5 X									GREEN ON WHITE SHEETING. INSTALL 100 FT ± EAST OF THE TH-29 INTERSECTION.	X		
		A	M1-5	30	24			5.00																					E-136B
EB	5.785	A	VW-054R	30	30								1		X															
		A	VW-054R	30	30			6.25								1		13.5 X											E-154
EB	6.780	A	W3-5	36	36								1		X															
		A	W3-5	36	36			9.00								2		15 14.3 X										X	
EB	6.860	A	VD-018	30	18		EAST CHARLESTON ISLAND POND 7			1				X															
EB	6.920	A	R2-1	24	30								1		X														
		A	R2-1	30	36			7.50								1		16.3 X									BEHIND RAIL		6	
EB	6.960	A	W11-8	36	36		FIRE ENGINE (SYMBOL)			1				X															
							SHEET TOTALS	36.00 SF	0.00 SF	5 EA	0 EA	0 EA	4 EA	0 EA	0 EA	6 EA		~~90~~ 87.6 FT											
							TOWN TOTALS	501.6	0.0	25.0	0.0	0.0	86	0.0	0.0	83		1245.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STGP SIGN(22)**

FILE NAME: **Charleston.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
CHARLESTON SHEET 6

PLOT DATE: **6/11/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **27** OF **79**