DIR	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHARLESTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	7.135	F	W1-2R	30	30		CURVE RIGHT						1		X			8.5		WINTER DAMAGE								
		F	D1-1	72	12		SEYMOUR LAKE	6.00								2		13.3 12.5 X								INSTALL BEHIND RAIL IN SAME POSITION AS JUST-REMOVED CURVE LEFT SIGN.		5	
		F	D1-1	72	12		ECHO LAKE	6.00																				5	
WB	7.090	G	VR-017	24	24		LEGAL LOAD LIMIT 24,0000 POUNDS						1		X												MILL ST (TH-47). DISCONTINUED, SIGN NO LONGER NEEDED.			
WB	7.082	H	R1-1	30	30		STOP						1		X												MILL ST (TH-47). DISCONTINUED, SIGN NO LONGER NEEDED.			
WB	7.077	A	W1-2Mi R	30	30			6.25 6.25					1			1		12.8 X		VTRANS PLAN ERROR, INCORRECT SIGN AND CORRECTED SIGN PAID.						INSTALL 25 FT ± WEST OF FORMER MILL STREET, NEXT TO POST OFFICE SIGN ±		6	
WB	7.070	F	D1-1G	54	7.5		SEYMOUR LAKE --->						1		X															
		F	D1-1G	54	7.5		ECHO LAKE --->						1																	
WB	7.060	G	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS						1		X												CHURCH HILL RD (TH-3)			
		G	VR-017	24	30			5.00 5.00			WINTER DAMAGE		1			1		13.5 X											E-141
WB	7.054	H	R1-1	24	24		STOP						1		X												CHURCH HILL RD (TH-3)			
		H	R1-1	30	30			6.25								1		11 X										X	
WB	6.980	F	M3-4	24	12		WEST			1				X															
		F	M1-5	30	24		VERMONT 105			1																			
WB	6.910	F	R2-1	24	30		SPEED LIMIT 50			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	40.75 ~~29.50~~	0.00	3	0	0	9 ~~7~~	0	0	5		~~75~~ 71.6											
VERMONT AGENCY OF TRANSPORTATION								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	501.6	0.0	25.0	0.0	0.0	86	0.0	0.0	83		1245.0											

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STGP SIGN(22)**

FILE NAME: **Charleston.xls** PLOT DATE: **6/11/2009**
PROJECT MANAGER: **N. Averv** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
CHARLESTON SHEET 9 SHEET **30** OF **79**