DIR	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHARLESTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	5.800	F	VW-054R	30	30		HIDDEN DRIVE RIGHT			1				X														
WB	5.645	F	W2-1Mb	30	30		4-WAY INTERSECTION SYMBOL			1				X														
WB	5.540	F	D1-1E	72	20		<--- CHARLESTON ELEMENTARY SCHOOL			1				X														
WB	5.410	F	R2-1	24	30			5.00								1		15 X								INSTALL 400 FT ± WEST OF 4-WAY INTERSECTION	X		
WB	4.740	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
WB	4.114	G	VR-017	24	24								1		X											WILLIS RD (TH-25)			
		G	VR-017	24	30			5.00								1		12.5 X										E-141
WB	4.106	H	R1-1	24	24								1		X											WILLIS RD (TH-25)			
		H	R1-1	30	30			6.25								1		12.3 X									X	
WB	2.552	F	W1-2L	30	30																					THIS DESCRIPTION INCORRECT. PAID R & S TO MOVE SIGN TO PROPER LOCATION ↓ INSTALL MIDWAY BETWEEN DRIVE TO "HILL SIDE DAYCARE" AND SMITH FARM RD (CLASS III SERVES ONLY ONE HOUSE)			
		F	W1-2L	30	30			6.25			1	1	1			1		15 X									X	
WB	2.260	F	W11-2YG	30	30	FYG	PEDESTRIAN SYMBOL			1				X														
		F	VW-387FY	24	18	FYG	DEAF CHILD PLAQUE			1																		
WB	2.200	F	M2-1	21	15								1		X													
		F	M1-5	24	24								1															
SIGN SUMMARY SHEET							SHEET TOTALS	22.50 SF	0.00 SF	5 EA	10 EA	10 EA	65 EA	0 EA	0 EA	4 EA		~~60~~ 54.8 FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	501.6	0.0	25.0	0.0	0.0	86	0.0	0.0	83		1245.0										

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STGP SIGN(22)**

FILE NAME: **Charleston.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
CHARLESTON SHEET 10

PLOT DATE: **6/11/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **31** OF **79**