DIR	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHARLESTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	1.450	F	W1-2L	30	30			6.25								1		15.8 X								INSTALL 300 FT ± WEST OF SPEED LIMIT 35 SIGN. MAINTAIN 10 FT MIN TO UTILITY POLE.	X		
WB	1.360	F	W11-2	30	30								1		X														
		F	W11-2PB	24	18								1																
		F	W11-2	30	30	FYG		6.25								1		15.5 X									X		
		F	W11-2PB	24	18	FYG		3.00																				6	
WB	1.255	G	VR-017	24	24																					DURGIN ROAD (TH-2)			
		G	VR-017	24	30			5.00								1		14 X											E-141
WB	1.247	H	R1-1	24	24								1		X											DURGIN ROAD (TH-2)			
		H	R1-1	30	30			6.25								1		14 X									X		
WB	1.105	F	W1-2L	30	30																								
		F	W1-1Md L	30	30			6.25								1		16.3 X								INSTALL MIDWAY BETWEEN UTILITY POLES, WEST OF DRIVE TO HOUSE #1129.		6	
		F	W16-8	30	8			1.67																		THIS ASSEMBLY WILL BE 250 FT ± EAST OF THE JCT WITH TH-6.		7	
WB	1.058	G	VR-017	24	24						1		1		X											FONTAINE ROAD (TH-6)			
		G	VR-017	24	30			5.00				1				1		15.5 X											E-141
WB	1.050	H	R1-1	24	24						1		2 ~~1~~		X											FONTAINE ROAD (TH-6)			
SIGN SUMMARY SHEET							SHEET TOTALS	39.67	0.00	0	~~1~~ 0	~~1~~ 0	~~6~~ 5	0	0	6		~~90~~ 91.1											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	501.6	0.0	25.0	0.0	0.0	86	0.0	0.0	83		1245.0											

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STGP SIGN(22)**

FILE NAME: **Charleston.xls** PLOT DATE: **6/11/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
CHARLESTON SHEET 13 SHEET **34** OF **79**