DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIGHTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	0.000	C	VD-024	72	10		BRIGHTON / CHARLESTON	5.00								2		13 13.3 X										
		C	VD-025	72	10		ESSEX CO / ORLEANS CO	5.00																				
		C	VD-700	6	10		1050 0504 0000 / 1050 1004 1003	0.42																	INSTALL BRIGHTON MM ON LEFT POST			E-138
		C	VD-700	6	10			0.42																	INSTALL CHARLESTON MM ON RIGHT POST			E-138
EB	0.480	A	W11-5	30	30								1		X													
		A	W11-5	30	30			6.25								1		15 X								X		
EB	0.605	A	W1-4R	30	30		RIGHT REVERSE CURVE W/ RH ROAD						1		X													
		A	W13-1	18	18		40 MPH PLAQUE						1															
EB	0.690	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
EB	0.700	A	W1-4R	30	30			6.25								1		14.8 X							INSTALL 50 FEET EAST OF EXISTING SCHOOL BUS STOP AHEAD SIGN	X		
		A	W13-1	18	18		40 M.P.H.	2.25																		X		
EB	0.735	A	VW-205	30	30		WATCH FOR TURNING VEHICLES						1		X													
EB	0.754	A	W2-2MaL	30	30			6.25								1		15.5 X									6	
EB	0.825	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		13 X							TH-9, BASIL HILL RD			E-141
EB	0.834	D	R1-1	24	24								1		X											TH-9, BASIL HILL RD			
SIGN SUMMARY SHEET							SHEET TOTALS	36.84	0.00	0	0	0	6	0	0	6		~~90~~ 84.6										
VERMONT AGENCY OF TRANSPORTATION								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	729.8	0.0	4.0	2.0	2.0	165	0.0	0.0	129		1935.0										

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**

FILE NAME: **Brighton.xls** PLOT DATE: **6/11/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **J. Kelly** CHECKED BY: **S. Menard**
BRIGHTON SHEET 1 SHEET **37** OF **79**