DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIGHTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	2.905	A	W1-10L	30	30		LEFT CURVE WITH RH SIDE ROAD						1		X														
		A	W13-1	18	18		35 MPH PLAQUE						1																
EB	2.945	A	W1-10L	30	30			6.25								1		16.8 X								INSTALL 200 FEET EAST OF EXISTING LEFT CURVE ASSEMBLY	X		
		A	W13-1	18	18			2.25																			X		
EB	2.987	C	VR-017	24	30								1		X												TH-18, CEDARWOOD DR			
		C	VR-017	24	30			5.00								1		13.8 X											E-141
EB	3.002	D	R1-1	24	24								1		X												TH-18, CEDARWOOD DR			
		D	R1-1	30	30			6.25								1		13.5 X									X		
EB	3.130	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X															
		A	W3-5	36	36			9.00								2		12.8 13.3 X											
EB	3.175	A	N/A	24	30		WARNING TO MOTORISTS ALL TRAFFIC LAWS ARE STRICTLY ENFORCED						1		X												SALVAGE TO TOWN			
EB	3.205	A	R2-1	24	30		SPEED LIMIT 35						1		X														
		A	VR-040	24	24		THROUGH WAY ENDS HERE						1																	
		B	VR-039	24	18		STATE HIGHWAY BEGINS						1																	
		A	VR-038	24	18			3.00								1		15 X											E-141
SIGN SUMMARY SHEET							SHEET TOTALS	31.75	0.00	0	0	0	9	0	0	6		~~90~~ 85.2											
VERMONT AGENCY OF TRANSPORTATION								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	729.8	0.0	4.0	2.0	2.0	165	0.0	0.0	129		1935.0											

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**
FILE NAME: **Brighton.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
PLOT DATE: **6/11/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
BRIGHTON SHEET 6
SHEET **42** OF **79**