DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIGHTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
WB	8.310	F	W1-2R	30	30		RIGHT CURVE						1		X														
WB	8.200	F	W1-2R	30	30			6.25								1		15.5 X								INSTALL 575 FEET WEST OF EXISTING ASSEMBLY	X		
		F	W13-1	18	18			2.25																			X		
WB	7.195	F	W11-6H	30	30		SNOWMOBILE(FOLDING)						1		X														
WB	6.515	F	W2-2L	30	30		SIDE ROAD LEFT						1		X														
WB	6.360	F	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
		F	W13-1	18	18		35 MPH PLAQUE						1																
WB	6.436	F	W1-4L	30	30			6.25								1		16.5 X								INSTALL 400 FEET WEST OF EXISTING ASSEMBLY	X		
		F	W13-1	18	18			2.25																			X		
WB	6.260 - 6.108	F/E		6	8		18 WHITE DELINEATORS	6.00								9		6.5 x 6 6.8 6.3 X 8								INSTALL BACK TO BACK AT 100 FT SPACINGS (6.260 - 6.108)		5	
WB	6.085	F	VD-062BRN	72	16		BUSINESS SIGN			1				X															
WB	6.060	F	VW-081R	30	30		TRUCKS ENTERING RIGHT						1		X														
WB	5.980	F	VW-081R	30	30			6.25								1		11.8 X								INSTALL 425 FEET WEST OF EXISTING ASSEMBLY		6	
WB	5.945	F	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
WB	5.755	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
							SHEET TOTALS	29.25	0.00	1	0	0	8	0	0	12		~~180~~ 103.9											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	729.8	0.0	4.0	2.0	2.0	165	0.0	0.0	129		1935.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**

FILE NAME: **Brighton.xls** PLOT DATE: **6/11/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **J. Kelly** CHECKED BY: **S. Menard**
BRIGHTON SHEET 14 SHEET **50** OF **79**