DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIGHTON VT 105							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	D2-1	72	10		DERBY CENTER 17						1																
WB	1.880	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
WB	1.850	F	VW-054L	30	30			6.25								1		14 X							INSTALL 150 FEET WEST OF EXISTING HIDDEN DRIVE SIGN			E-154
WB	1.844	G	VR-017	24	30								1		X															
		G	VR-017	24	30			5.00								1		14.3 X							TH-15, FIVE MILE SQUARE RD			E-141
WB	1.836	H	R1-1	30	30								1		X															
		H	R1-1	30	30			6.25								1		14 X							TH-15, FIVE MILE SQUARE RD	X		
WB	1.73-1.60	F/E		6	8		16 DELINEATORS	5.33								8	6.5 x 6 6 x 2 X									INSTALL BACK TO BACK AT 100' SPACING ALONG OUTSIDE OF CURVE		5	
WB	1.555	F	W11-4	30	30		CATTLE						1		X														
WB	1.460	F	W1-2R	30	30			6.25								1		15.3 X							INSTALL AT EAST CORNER OF DRIVEWAY	X		
WB	1.035	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		F	W13-1	18	18		40 MPH PLAQUE						1																
WB	0.997	F	W1-4R	30	30			6.25								1		17 X							INSTALL 200 FEET EAST OF EXISTING ASSEMBLY	X		
		F	W13-1	18	18			2.25																			X		
WB	0.954	F	W11-5	30	30			6.25								1		16.8 X							INSTALL 225 FEET EAST OF NEW REVERSE CURVE ASSEMBLY	X		
SIGN SUMMARY SHEET							SHEET TOTALS	43.83	0.00	0	0	0	7	0	0	14		~~210~~ 142.4										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	729.8	0.0	4.0	2.0	2.0	165	0.0	0.0	129		1935.0										

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**
FILE NAME: **Brighton.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
BRIGHTON SHEET 21
PLOT DATE: **6/11/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **57** OF **79**