| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB/FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB/FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB/FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BLOOMFIELD VT 105** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | E | M6-1R | 21 | 15 | | | 2.19 | | | | | | | | | | | | | | | | | | GREEN ON WHITE SHEETING | X | | |
| | | F | M3-4 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | | INSTALL ON BACK OF EB FACING ASSEMBLY, ON POST CLOSEST TO ROAD. GREEN ON WHITE SHEETING | X | | |
| | | F | M1-5 | 30 | 24 | | | 5.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| WB | 4.155 | F | M3-4 | 24 | 12 | | WEST | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | M1-5 | 30 | 24 | | VT 105 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | 15.5<br>X | | | | | | | | | X | | |
| WB | 4.135 | F | VR-601 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | VR-601 | 30 | 36 | | | 7.50 | | | | | | | | 1 | | 16<br>X | | | | | | | | | | 5 | |
| WB | 4.115 | G | VR-017 | 24 | 24 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | G | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | 13.5<br>X | | | | | | | | | TH-9, SPENCER HILL RD | | | E-141 |
| WB | 4.105 | H | R1-1 | 24 | 24 | | | | | | | | 2<br>~~1~~ | | X | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 11.5<br>X | | | | | | | | | TH-9, SPENCER HILL RD | X | | |
| WB | 4.100 | F | VR-048 | 24 | 30 | | SCHOOL BUS LAW | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 4.080 | F | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 32.94 | 0.00 | 0 | 0 | 0 | ~~8~~ 9 | 0 | 0 | 4 | | ~~60~~ 56.5 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 427.5 | 0.0 | 2.0 | 0.0 | 0.0 | 87 | 0.0 | 0.0 | 59 | | 885.0 | | | | | | | | | | |

PROJECT NAME: **Derby-Bloomfield VT105**
PROJECT NUMBER: **STPG SIGN(22)**

FILE NAME: **Bloomfield.xls** PLOT DATE: **6/11/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
BLOOMFIELD SHEET 9 SHEET **73** OF **79**