DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
SHOREHAM VT22A							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.000	C	VD-024	60	7.5								1																
		C	VD-024	72	10		SHOREHAM / ORWELL 0221 0118 0000 / 0221 0114 0643	5.00								2		X									4	
		C	VD-700	6	10			0.42																					E-138
		C	VD-700	6	10			0.42																					E-138
NB	0.348	A	W11-5	30	30		FARM MACHINERY WARNING						1		X														
NB	0.425	A	W11-5	30	30			6.25								1		X									X		
NB	0.741	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1														TH-44, BROWN RD			
		C	VR-017	24	30			5.00								1		X											E-141
NB	0.749	D	R1-1	30	30		STOP					1	1														TH-44, BROWN RD			
		D	R1-1	30	30			6.25								1		X										X	
NB	1.270	C	VR-023b	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	5.00					1			1		X									INSTALL AT MID-POINT OF LARG PULL-OFF			E-144
NB	2.396	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
NB	2.425	A	W3-5	36	36		SPEED LIMIT 40	9.00								2		X									INSTALL 150 FEET NORTH OF EXISTING REDUCED SPEED AHEAD SIGN	X		
NB	2.434	A	VD-018	30	18		VILLAGE SIGN						1		X														
NB	2.472	A	W2-1	30	30		CROSSROADS						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	37.34 SF	0.00 SF	0 EA	0 EA	0 EA	8 7 EA	0 EA	0 EA	8 EA		120 FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	569.3	0.0	6.0	2.0	2.0 1	132	1.0	0.0	77		1155.0										

PROJECT NAME: **Fair Haven-Panton VT22A**
PROJECT NUMBER: **STPG SIGN(24)**
FILE NAME: **Shoreham.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
SHOREHAM SHEET 1
PLOT DATE: **4/29/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **55** OF **117**