DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) (LB / FT) 1.75 / 2.00 / 2.50	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 3.50 / 4.00 / 5.00	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
																	1.88 / 2.42 / 3.35	7.60 / 9.00 / 10.80 / 14.60						
SHOREHAM VT22A							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN														"SHS"-STANDARD HIGHWAY SIGNS			
		A	M1-5	24	24			4.00																E-136B
NB	2.680	A	VD-062B	72	16		BUSINESS SIGN			1				X										
		A	VD-062B	72	16		BUSINESS SIGN			1														
NB	2.728	A	VW-202	30	30		TRUCKS ENTERING WARNING						1		X									
NB	2.766	A	R2-1	24	30								1		X			X						
		A	R2-1	24	30			5.00								1							X	
NB	2.963	A	M2-1	21	15								1		X									
		A	M1-5	24	24								1											
		A	M2-1	21	15			2.19								1		X			GREEN ON WHITE SHEETING	X	
		A	M1-5	24	24			4.00																E-136B
NB	2.990	A	D9-1	24	30		PHONE SYMBOL						1		X									
		A	VD-058	24	8		PHONE ARROW						1											
NB	3.005	A	D1-1A	72	10								1		X									
		A	D1-1A	72	10								1											
		A	D1-1M	72	10								1											
SIGN SUMMARY SHEET							SHEET TOTALS	15.19 SF	0.00 SF	2 EA	0 EA	0 EA	9 EA	0 EA	0 EA	2 EA	30 FT							
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	569.3	0.0	6.0	2.0	2.0	132	1.0	0.0	77	1155.0							

PROJECT NAME: **Fair Haven-Panton VT22A**
PROJECT NUMBER: **STPG SIGN(24)**

FILE NAME: **Shoreham.xls** PLOT DATE: **4/29/2009**
PROJECT MANAGER: **N. Averv** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **J. Kelly** CHECKED BY: **S. Menard**
SHOREHAM SHEET 3 SHEET **57** OF **117**