DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SHOREHAM VT22A							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M3-3	24	12			2.00																		GREEN ON WHITE SHEETING	X		
		F	M1-5A	24	24			4.00																					E-136B
SB	3.000	F	VW-202	30	30		TRUCKS ENTERING						1		X														
SB	2.970	F	D2-1	72	10		ORWELL DESTINATION SIGN						1		X														
		F	D2-1	72	10		FAIR HAVEN DESTINATION SIGN						1																
		F	M3-3	24	12		SOUTH						1																
		F	M1-5A	24	24		ROUTE 22A						1																
SB	2.880	F	R2-1	24	30			5.00								1		X								INSTALL 475 FEET SOUTH OF EXISTING D-BOARDS AND ROUTE MARKERS.	X		
SB	2.710	F	W2-1	30	30		CROSSROAD WARNING						1		X														
SB	2.700	F	W2-1Mb	30	30			6.25								1		X								INSTALL 50 FEET SOUTH OF EXISTING CROSSROAD SIGN		6	E-155
SB	2.660	F	D1-1A	72	12		WHITING 5	6.00								2		X								INSTALL 200 FEET NORTH OF INTERSECTION		5	
SB	2.646	F	D1-1A	72	10		WHITING DESTINATION SIGN						1		X														
SB	2.624	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											TH-31, CEMETERY RD			
		G	VR-017	24	30			5.00								1		X								INSTALL BELOW EXISTING SALVAGED SL 35			E-141
		G	R2-1	24	30		SPEED LIMIT 35				1																		
							SHEET TOTALS	28.25 SF	0.00 SF	0 EA	1 EA	0 EA	8 EA	0 EA	0 EA	5 EA		75 FT										
							TOWN TOTALS	569.3	0.0	6.0	2.0	2.0	132	1.0	0.0	77		1155.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Fair Haven-Panton VT22A**
PROJECT NUMBER: **STPG SIGN(24)**

FILE NAME: **Shoreham.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
SHOREHAM SHEET 17

PLOT DATE: **4/29/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **71** OF **117**