DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIDPORT VT22A							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W13-1	18	18	FY		2.25																			X		
SB	4.335	F	S3-1	30	30		SCHOOL BUS STOP AHEAD	6.25					1			1		X								INSTALL 150 FEET SOUTH OF INTERSECTION	X		
SB	4.211	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X														
		G	VR-017	24	30			5.00								1		X								TH-19, SAWMILL RD			E-141
SB	4.203	H	R1-1	30	30							2	1		X														
		H	R1-1	30	30		STOP	6.25								1		X								TH-19, SAWMILL RD	X		
SB	4.160	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
SB	4.080	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
SB	4.050	F	W3-5	36	36		SPEED LIMIT 40	9.00								2		X								INSTALL 150 FEET SOUTH OF EXISTING REDUCED SPEED AHEAD SIGN.	X		
SB	4.010	F	VD-018	30	18		BRIDPORT SHOREHAM 7						1		X														
		F	VD-018	30	18			3.75								1		X											E-128A
SB	3.970	F	M2-1S	21	15								1		X														
		F	M1-5	30	24		JCT VERMONT 125						1																
		F	M2-1S	21	15			2.19								1		X								GREEN ON WHITE SHEETING	X		
		F	M1-5	30	24			5.00																					E-136B
SIGN SUMMARY SHEET							SHEET TOTALS	39.69 SF	0.00 SF	1 EA	0 EA	~~2~~ 0 EA	~~7~~ 6 EA	0 EA	0 EA	7 EA			105 FT									
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	750.3	0.0	11.0	0.0	0.0	175	0.0	0.0	115			1725.0									

PROJECT NAME: **Fair Haven-Panton VT22A**
PROJECT NUMBER: **STPG SIGN(24)**

FILE NAME: **Bridport.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
BRIDPORT SHEET 14

PLOT DATE: **4/29/2009**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **S. Menard**
SHEET **87** OF **117**