| DIR | MILEPOINT | LOCATION CODE (SHEET 2) | MUTCD CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND<br>FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (in) (LB / FT) 1.75 / 1.88 | SQUARE STEEL (in) (LB / FT) 2.00 / 2.42 | SQUARE STEEL (in) (LB / FT) 2.50 / 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60 | TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00 | TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80 | TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **ADDISON VT22A** | | | | | | | "FY"-FLUORESCENT YELLOW<br>"FYG"-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 3.000 | A | R2-1 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | X | |
| NB | 3.750 | A | VD-062BRN | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | VD-062AL | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | |
| NB | 3.844 | A | W3-5 | 36 | 36 | | SPEED REDUCTION 35 | | | 1 | | | | X | | | | | | | | | | | | | | |
| NB | 3.895 | A | VD-018 | 30 | 18 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | VD-018 | 30 | 18 | | | 3.75 | | | | | | | | 1 | | X | | | | | | | | | | E-128A |
| NB | 3.935 | A | R2-1 | 30 | 36 | | SPEED LIMIT 35 | | | 1 | | | | X | | | | | | | | | | | | | | |
| NB | 3.978 | A | W2-1 | 36 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | A | W11-8 | 36 | 36 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | W2-1 | 36 | 36 | | | 9.00 | | | | | | | | 2 | | X | | | | | | | | | X | |
| | | A | W11-8 | 36 | 36 | | | 9.00 | | | | | | | | | | | | | | | | | | | X | |
| NB | 4.012 | A | M2-1S | 21 | 15 | | JCT VT 17 | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | VERMONT 17 | | | 1 | | | | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 26.75 SF | 0.00 SF | 7 EA | 0 EA | 0 EA | 4 EA | 0 EA | 0 EA | 4 EA | 60 FT | | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 357.4 | 0.0 | 58.0 | 0.0 | 0.0 | 69 | 1.0 | 0.0 | 56 | 840.0 | | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Fair Haven-Panton**
PROJECT NUMBER: **STPG SIGN(24)**

FILE NAME: **Addison.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
ADDISON SHEET 4

PLOT DATE: **4/29/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **S. Menard**
SHEET **101** OF **117**