DIR	MILEPOINT	LOCATION CODE (SHEET 2)	MUTCD CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND FOR ALL POST LENGTHS SEE ORIGINAL RECORD PLANS	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
ADDISON VT22A							"FY"-FLUORESCENT YELLOW "FYG"-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	D1-1M	72	10								1																
		F	D1-1A	72	12			6.00								2		X									5	
		F	D1-1A	72	12	CHARGED 72X10		6.00																			5	
		F	D1-1A	72	12			6.00																			5	
		F	D1-1M	72	12			6.00																			5	
SB	4.235	F	R8-3A	24	24								1		X														
		F	VR-644	24	12								1																
		F	R8-3A	24	24			4.00								1		X									X	
		F	VR-644	24	12			2.00																			6	
SB	4.200	F	M3-2	24	12		ROUTE MARKERS						1		X														
		F	M1-5A	24	24								1																
		F	M6-1	21	15								1																
		F	M3-3	24	12								1																
		F	M1-5A	24	24								1																
		F	M6-3	21	15								1																
							SHEET TOTALS	30.00 SF	0.00 SF	0 EA	0 EA	0 EA	9 EA	0 EA	0 EA	3 EA	45 FT											
							TOWN TOTALS	357.4	0.0	58.0	0.0	0.0	69	1.0	0.0	56	840.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Fair Haven-Panton**
PROJECT NUMBER: **STPG SIGN(24)**

FILE NAME: **Addison.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
ADDISON SHEET 10

PLOT DATE: **4/29/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **S. Menard**
SHEET **107** OF **117**