TOWN TOTAL SIGN SUMMARY SHEET

VT ROUTE 22A **Fair Haven - Panton STPG SIGN (24)**

Townname	County	TWN_TMM	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		NUMBER OF NEW POSTS (EA)				SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED
											1.75"	2"	2.5"		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00	5.00	
											(LB / FT)				(LB / FT)				(LB / FT)				
			TYPE A	TYPE B	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	1.88	2.42	3.35	TOTAL POSTS	1.88	2.42	3.35		7.60	9.00	10.80	14.60	
								143															
Fair Haven	Rutland	4.43	601.5	0	9	5	9 ~~5~~	~~137~~	0	0	0	89	6	95	0	1335	90	1174.25		89.25			
West Haven	Rutland	3.007	100.2	0	7	2	2	19 ~~13~~	0	0	5	17	0	22	~~75~~	255	0	222.25		0			
Benson	Rutland	6.276	408	0	12	3	10 ~~3~~	91 ~~74~~	0	0	0	69	2	71	0	1035	30	926.83		31.5			
Orwell	Addison	6.429	339.7	0	9	3	5 ~~3~~	76 ~~67~~	0	2	0	38	0	38	0	570	0	517		0			
Shoreham	Addison	6.384	569.3	0	6	2	8 ~~2~~	~~132~~	1 ~~52~~	1	0	73	4	77	0	1095	60	995.5		91.5			
Bridport	Addison	6.301	750.3	0	11	0	25 ~~0~~	~~175~~	20 ~~20~~	0	0	111	4	115	0	1665	60	1487.83		60.25			
Addison	Addison	6.315	357.4	0	58	0	9 ~~0~~	81 ~~69~~	1	0	0	54	2	56	0	810	30	695.67		30			
Panton	Addison	2.755	81.7	0	1	2	2	17 ~~12~~	0	0	16	14	0	30	~~240~~	210	0	215.75		0			
															133.33	6235.08							
							70	781					174.98	~~315~~	~~6975~~	~~270~~	272.5						
		TOTAL =	3208.1	0	113	17	~~17~~	~~679~~	2	2	21	465	18	504	~~7560~~			0	0	0	0	0	0
															6682.56								

Estimated Salvaged Street Name Signs to be erected onto new posts = 20

PROJECT NAME: FAIR HAVEN - PANTON

PROJECT NUMBER: STPG SIGN (24)

FILE NAME: 09b030_TS.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
TOWN TOTAL SIGN SUMMARY SHEET

PLOT DATE: 30-APR-2009
DRAWN BY: N. AVERY
CHECKED BY: A. GAMBLE
SHEET 115 OF 117