DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
HALIFAX VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W1-8	18	24	FY		3.00								1		13 X									X	
		B	W1-8	18	24	FY		3.00								1		13 X									X	
NB	3.445	A	W1-8	18	24								1		X													
		B	W1-8	18	24								1															
		A	W1-8	18	24	FY		3.00								1		13 X									X	
		B	W1-8	18	24	FY		3.00								1		13 X									X	
NB	3.552	C	VR-017	24	30								1		X											HUBBARD HILL ROAD (TH-28)		
		C	VR-017	24	30			5.00								1		13.5 X										E-141
NB	3.556	D	R1-1	30	30		HUBBARD HILL RD. 				I	I	1		X											HUBBARD HILL ROAD (TH-28)		
		D	R1-1	30	30			6.25								1		13.5 X									SALVAGE ROAD SIGN NEW POST. PAY AS ITEM 675.60	X	
NB	3.570	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
NB	3.640	A	W1-2R	30	30		CURVE RIGHT						1		X													
		A	VW-054R	30	30		HIDDEN DRIVE RIGHT 						1															
		A	W13-1	18	18		40 MPH (PLAQUE) 						1													INCORRECT SYMBOL			
NB	3.660	A	W1-2R	30	30	FY		6.25								1		15 X									INSTALL 100 FT ± NORTH OF PREVIOUS LOCATION	X	
							SHEET TOTALS	29.50 SF	0.00 SF	0 EA	0 EA	0 EA	8 EA	0 EA	0 EA	7 EA			~~105~~ 94 FT								
							TOWN TOTALS	640.7 SF	0.0 SF	5.0 EA	10.0 EA	10.0 EA	176 EA	0.0 EA	0.0 EA	111 EA			1665.0 FT								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Halifax-Whitingham VT112**
PROJECT NUMBER: **STPG SIGN(26)**

FILE NAME: **Halifax.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
HALIFAX SHEET 11

PLOT DATE: **6/22/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **S. Menard**
SHEET **18** OF **46**