DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
HALIFAX VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W13-1	18	18	FY		2.25																			X	
NB	3.690	A	VW-054A	30	30	FY	HIDDEN DRIVE RIGHT	6.25								1		I5 X								INSTALL160 FT ± NORTH OF CURVE RIGHT SIGNS.		E-154
NB	4.115	A	W1-1L	30	30		TURN LEFT						1		X													
		A	W13-1	18	18		30 MPH PLAQUE						1																
		A	W1-1Md L	30	30			6.25								1		I5 X										6
		A	W13-1	18	18		30 M.P.H.	2.25																			X	
NB	4.151	C	VR-017	24	30								1		X											LARRABEE ROAD (TH-27) SOUTHERLY JCT OF THIS "Y" INTERSECTION		
		C	R2-1	18	24		SPEED LIMIT 35				1																	
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		I5 X										E-141
		C	R2-1	18	24		SPEED LIMIT 35					1														SALVAGE THE TOWN INSTALLED SPEED LIMIT SIGN UNDER THE NEW LEGAL LOAD LIMIT SIGN.		
NB	4.159	D	R1-1	30	30		STOP						1		X											LARRABEE ROAD (TH-27)		
		D	R1-1	30	30			6.25								1		I3.5 X									X	
NB	4.165	A	W1-6	48	24								1		X													
		A	OM1-1	18	18		OBJECT MARKER						1																
		A	W1-6	48	24			8.00								2		I3 I3 X									X	
SIGN SUMMARY SHEET							SHEET TOTALS	36.25 SF	0.00 SF	0 EA	1 EA	1 EA	6 EA	0 EA	0 EA	6 EA	~~90~~ 84.5 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	640.7 SF	0.0 SF	5.0 EA	10.0 EA	10.0 EA	176 EA	0.0 EA	0.0 EA	111 EA	1665.0 FT											

PROJECT NAME: **Halifax-Whitingham VT112**
PROJECT NUMBER: **STPG SIGN(26)**

FILE NAME: **Halifax.xls** PLOT DATE: **7/7/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
HALIFAX SHEET 12 SHEET **19** OF **46**